



TeSys

TeSys Control - Giga Contactors
TeSys Protect - Giga Electronic Overload Relays
Catalogue 2021



se.com/tesys

Life Is On

Schneider
Electric

Authorized Partner

 **wedco** inc.
Reno Winnemucca Fallon Stateline Carson City



Start smart. Run smart. With TeSys™ motor controls.

Stay smart with the world's best-selling motor control solutions from the inventor of the world's first contactor – Schneider Electric™.


For almost a century, TeSys™ motor controls have driven the industry with innovations in motor protection, monitoring, and control.

It started with the introduction of the industry's first BAR contactor in 1924, and today, the legacy of innovation is built into every TeSys motor control device.

Best-in-class safety and reliability, plug-and-play architecture, and flexible functionality mean TeSys motor control solutions can meet your requirements across a wide range of applications, from the most common to the most advanced.

Wherever you are and anywhere your projects come together, you can trust Schneider Electric and TeSys contactors, circuit breakers, relays, and switches for unmatched reliability, complete compatibility with international standards, and the robust support of the Schneider Electric global supply network.

Start smart, run smart and stay smart with TeSys motor controls.



TeSys Control

Giga Contactors

- Used for **TeSys** Control function
- New generation of high power contactors 115-800 A ⁽¹⁾ (AC-3)
- Less product references for easier selection and reduced inventory
- Designed to meet needs of demanding applications
- Width and depth alignment with overload relays and breakers for easier connection
- Compact design for less installation space consumption
- Coil designed for less energy consumption and wider voltage band-width
- Advanced contact wear diagnostic for predictive maintenance
- Modularity design for easy maintenance and short down times



TeSys Protect

Giga Electronic Overload Relays

- Used for **TeSys** Protect function
- New generation of electronic overload relays 28-630 A ⁽²⁾
- Less product references for easier selection and less inventory
- Compatible with **TeSys** Giga Contactors
- Wide setting range with advanced protections
- Full set of features for more flexibility
- Continuous monitoring with health and alarm indicators



⁽¹⁾ 630 A and 800 A contactors shall be launched in Q1 2022.

⁽²⁾ 630 A overload relay shall be launched in Q1 2022.

> Designed for evolution

On-line tools to configure your motor starters

EcoStruxure™ Motor Control Configurator



Scan or click
on the QR code

Build your starter configuration

- Build your motor starter configuration with different solutions
- Complete offer base suited for different countries.

Enhanced customer's journey

- Easy selection, replacing complex paper catalogs
- Convert into Bill of Materials (BoM) by adding the products to the cart.

Answers to customer needs

- Option to save and re-work your configurations
- Direct access to products documentation in one place
- Possibility with unique configurations ID and share.

Product Selector for TeSys Giga



Scan or click
on the QR code

Offer selection

- Easy selection of **TeSys** Giga Contactor or Overload Relays
- Intuitive tool to configure the devices to suit your needs
- Helps to select the right devices for your application.

Configure your motor starter components

- Options to select auxiliaries and accessories
- Configure reversers and changeover contactors with ease
- Get the extensive bill of material, export it in standard format (PDF, XLS), or drop it into the product cart
- Access to technical information and documentations for every item.

EcoStruxure Motor Management Design



Scan or click
on the QR code

Electrical design calculations for high-power motors

Easily perform basic calculations related to transformer size, short-circuit current and voltage drop, comparing direct-on-line, star-delta, soft-starter, and variable speed drive. Verify starting feasibility from mechanical standpoint and ensure power quality objectives are met, for power factor or harmonic levels. Check energy saving potential of using a variable speed drive for centrifugal pumps and fans.

Offer selection and report

Select among latest compatible offers to build a complete motor management solution: circuit breakers, contactors, MCC panels, drives, protection relays, power factor capacitors, active filters, power quality monitoring and services.
Get a summary report with calculations and recommended offers.

TeSys Control


TeSys Protect

General contents

TeSys Control – Giga Contactors	5
Introduction.....	6
Description	9
Product references	12
Technical data for designers.....	23
 TeSys Protect – Giga Electronic Overload Relays.....	 35
Introduction.....	36
Description	37
Product references	38
Technical data for designers.....	39
 TeSys Giga series - Device selection	 45
Coordination tables	
TeSys Giga Contactors for various applications	

Product references – coding principle


> TeSys Giga Contactors



Example:

LC1G400LSEA TeSys Giga Contactor Advanced version 400 A, 3 pole, 200...500 V AC/DC coil, with PLC control.
LC1G1854EHEN TeSys Giga Contactor Standard version 185 A, 4 pole, 48...130 V AC/DC coil, without PLC control.

> TeSys Giga Electronic Overload Relays



⁽¹⁾ Launch in Q1 2022.

TeSys Control Giga Contactors

TeSys Giga Contactors			
Type of product	Range		Pages
Introduction			6
TeSys Giga Contactors Advanced version - 3 and 4 poles	3-pole from 115 to 800 A – AC-3 ⁽¹⁾ 3-pole, 4-pole from 250 to 1050 A – AC-1 ⁽¹⁾		12
TeSys Giga Contactors Standard version - 3 and 4 poles	3-pole from 115 to 800 A – AC-3 ⁽¹⁾ 3-pole, 4-pole from 250 to 1050 A – AC-1 ⁽¹⁾		14
Auxiliary modules, Accessories, Retrofit kits for TeSys Giga Contactors			16
Spare parts for TeSys Giga Contactors			21
Technical Data for Designers			23

⁽¹⁾ 630 A and 800 A (AC-3) and 1050 A (AC-1) contactors shall be launched in Q1 2022.

TeSys Giga

A new Generation series with digital innovation

Over more than 4 decades, the **TeSys F** range of contactors has built a high reputation for performance, reliability, and quality. The **TeSys F** range set the industrial standard for high power contactors with an installed base of millions of products. **TeSys F** contactors were the first choice of many OEMs, control panel builders and industrial users.

But industry requirements have evolved to demand process performance monitoring through data networks and online expert services.

TeSys Giga is Schneider Electric's new range of contactors that answer these evolving needs. TeSys Giga Contactors support the evolution of processes and offer new services to reduce non-production time to a minimum. Replacing **TeSys F** Contactors, TeSys Giga Contactors address a wide range of demanding applications with built-in advanced features and functionalities.



Futuristic ready...


TeSys Giga Contactors are designed to work with components and accessories with advanced performance. The characteristics of robustness and longevity are maintained, both in the connectors and in the switching.

Continuous local and remote monitoring of contact wear optimizes predictive maintenance by allowing you to replace contacts only when necessary, facilitated by diagnostic visual indicator.

Every customer will benefit from the innovative design and feature, including the compact size, wideband electronic coils, embedded auxiliary contact blocks, ergonomic design, or flexibility in connections.

> Quality and Performance as high priority

> Applications



AC-3/AC-3e utilization category

AC-1 utilization category

- TeSys Giga Contactors provide robust control solutions for AC-3/AC-3e applications up to 800 A ⁽¹⁾ (450 kW) and AC-1 applications up to 1050 A ⁽¹⁾.
- TeSys Giga Contactors can be part of a direct-on-line motor starter, reversing motor starter or a star-delta motor starter and power switching application.
- TeSys Giga Contactors provide contact wear diagnostic and wideband AC/DC control.
- Suitable for type 2 coordination as per IEC60947-4-1.

> Right choice for a wide range of demanding applications




TeSys Giga Contactors' unique design meets the common requirements of demanding high power applications:

- Conform to multi standards to suit global needs
- Long life expectancy in harsh environments
- Suitable for high efficiency motors
- Very good resistance to vibrations
- High uptime thanks to predictive maintenance
- Optimized installation and maintainability.

⁽¹⁾ 630 A and 800 A (AC-3) and 1050 A (AC-1) contactors shall be launched in Q1 2022.

> Intelligent design for greater advantages



Higher flexibility

TeSys Giga Contactors can be mounted in different orientation without derating, providing high flexibility of your panel design.

Control wiring, auxiliary contacts and control module are accessible from the front.



Contact wear diagnostic and predictive maintenance

Contact wear is monitored by a dedicated module and shown in the front panel through LED, therefore the, predictive maintenance can be planned for replacing the complete set of switching modules, thus avoiding break-down maintenance. Switching modules ⁽¹⁾ can be replaced quickly and easily thanks to their Plug and Play design.

⁽¹⁾ Refer to page 22 for details on switching modules.

> Key features

Advanced contactor control

- The electronic control module provides wideband AC/DC coil control voltage, from 24 V to 500 V, allowing quick adaptation of existing industrial processes as well as new projects.
- The low power consumption of the coils could lead to significant savings on automation equipment. It's now possible to use interface relays with a lower rating, resulting in lower heat emission in the panel.
- The low power consumption of the coils also takes up less space in the panel and simplifies the diagrams by connecting these coils directly to the output cards of the PLCs.

Simplified wiring

- The pole pitch of the power terminals allows direct mounting and connection to **TeSys Giga** Electronic Overload Relays. Standardization of panel mounting and assembly reduces costs and assembly time.
- Push-in connection for control terminals provides flexibility, ease of connections, and reduced assembly and installation time.

Enhanced durability

- Durability is a top priority. **TeSys Giga** Contactors are designed to offer uncompromising robustness and maintenance accessibility to site technicians. The duration of production downtime is reduced, resulting in improved profitability on your investment.

Advanced diagnostic features


- On-board diagnostics is a new feature in our latest generation of high power contactors. Counting the number of operations as well as monitoring duration of use and pole condition provides numerous benefits for the customer and improves reliability and maintenance planning.

Compact size

- Compact size provides easy access to power connections for connecting cables and busbars.

Easy maintenance

- The poles are designed as replaceable switching modules, so the performance of a used contactor can be fully restored. The modular design allows a quick and long-lasting replacement.
- Coils are accessible from the front and maintained with very low down times.



*: product references finishing by A or N.

A comprehensive range of TeSys Giga Contactors that are available in 'Advanced' and 'Standard' versions, in 3 sizes, covering several ratings.

A common range of auxiliary contacts and accessories, enabling high flexibility and simplicity.

> TeSys Giga Contactors – Advanced version



115...225 A



265...500 A

Power & control

- 3 or 4 power poles
- 115 to 800 A ⁽¹⁾ (AC-3)
- 200 to 1050 A ⁽¹⁾ (AC-1)
- Embedded 1 NO + 1 NC auxiliary contacts
- Push-in type terminals for coils & control

Remote control

- 24-48 V, 48-130 V, 200-500 V AC/DC coils
- Low consumption coils
- Wide voltage range coils (direct coil control)
- Digital control input (PLC output digital coil control)
- Embedded surge suppressor

Diagnostic

- Embedded wear diagnostic
- Embedded control voltages diagnostic
- Self diagnosis function
- Local alarm signaling (LED)
- Remote wear diagnostic signaling kit (accessory)

Mounting

- 'Cabling memory' adapter enables maintenance without removing power cables and busbar connections.

Standards and Certifications

- Multiple standards
- International certifications

> TeSys Giga Contactors – Standard version



115...225 A



265...500 A

Power & control

- 3 or 4 power poles
- 115 to 800 A ⁽¹⁾ (AC-3)
- 200 to 1050 A ⁽¹⁾ (AC-1)
- Embedded 1 NO + 1 NC auxiliary contacts
- Push-in type terminals for coils & control

Remote control

- 48-130 V, 100-250 V AC/DC coils
- Wide voltage range coils (direct coil control)
- Embedded surge-suppressor


Diagnostic

- Embedded wear diagnostic
- Embedded control voltages diagnostic
- Self diagnosis function
- Local alarm signaling (LED)

Certifications

- Multiple standards
- International certifications

⁽¹⁾ 630 A and 800 A (AC-3) and 1050 A (AC-1) contactors shall be launched in Q1 2022.



- ① Cable memory kit **LA9G3102**, is always supplied along with Advanced version, and it's an optional accessory for Standard version.
- ② Mechanical interlock **LA9G970**, can be installed on either side of the contactor.
- ③ Auxiliary contact module **LAG8N113P** (1 NO + 1 NC) supplied with LC1G contactor.
- ④ Auxiliary contact modules **LAG8N113P / LAG8N203P**, can be installed on the contactor lateral faces ⁽¹⁾
- ⑤ Auxiliary contact modules **LAG8N113 / LAG8N203**, can be installed on either side as 2nd set of contacts.
- ⑥ Remote Wear Diagnostic (RWD) Module **LA9GRD01 / LA9GRD10**, can be installed and used only in Advanced version.
- ⑦ IP 20 terminal shroud **LA9G3701**.
- ⑧ Phase separators **LA9G3801**, please refer to pages 16 to 19 for complete details of available accessories.

Note: a maximum of 2 auxiliary contact modules can be mounted on each side of the contactor.
(1) Does not increase the contactor dimensions even when fitted on both sides.

TeSys Giga 3-pole Advanced contactors – For motor control (115 to 800 A)



Motor ratings (kW) $\theta \leq 60^\circ\text{C}$

IEC


AC-3

AC-3e ⁽¹⁾

AC-4

230 V	400 V	415 V	440 V	500 V	690 V	1000 V	230 V	400 V	415 V	440 V	500 V	690 V	1000 V	230 V	400 V	415 V	440 V	500 V	690 V	1000 V
kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW
30	55	55	75	75	75	-	30	55	55	75	75	75	-	30	55	55	65	65	75	-
37	75	75	90	90	90	75	37	75	75	90	90	90	75	37	75	75	80	90	90	75
55	90	90	110	110	110	75	55	90	90	110	110	110	75	55	90	90	100	110	110	75
55	110	110	132	132	160	132	55	110	110	132	132	160	132	55	110	110	129	132	132	110
75	132	132	160	160	200	160	75	132	132	160	160	200	160	75	132	132	150	160	160	160
90	160	160	200	200	220	185	90	160	160	185	200	220	185	90	160	160	185	200	220	185
110	200	200	250	250	315	220	110	200	200	250	250	315	220	110	200	200	220	250	315	220
160	250	250	315	355	355	335	147	250	250	280	315	355	335	150	250	250	295	295	355	280
200	335	375	400	400	500	450	180	315	335	355	375	500	450	180	315	335	355	375	450	355
250	450	450	450	500	560	450	200	335	355	375	425	560	450	200	375	355	375	400	475	400

TeSys Giga 3-pole and 4-pole Advanced contactors for load control only (non motor) – (250 to 1050 A / 690 V)



Maximum current (A) ($\theta \leq 40^\circ\text{C}$)	General purpose continuous current (A)	Reference					
IEC	UL	Advanced version contactors					
		AC/DC coil voltage					
AC-1		3 Pole			4 Pole		
		24...48 V ⁽²⁾	48...130 V ⁽²⁾	200...500 V	24...48 V ⁽²⁾	48...130 V ⁽²⁾	200...500 V
250	210	LC1G115BEEA	LC1G115EHEA	LC1G115LSEA	LC1G1154BEEA	LC1G1154EHEA	LC1G1154LSEA
275	230	LC1G150BEEA	LC1G150EHEA	LC1G150LSEA	LC1G1504BEEA	LC1G1504EHEA	LC1G1504LSEA
305	250	LC1G185BEEA	LC1G185EHEA	LC1G185LSEA	LC1G1854BEEA	LC1G1854EHEA	LC1G1854LSEA
330	290	LC1G225BEEA	LC1G225EHEA	LC1G225LSEA	LC1G2254BEEA	LC1G2254EHEA	LC1G2254LSEA
385	340	LC1G265BEEA	LC1G265EHEA	LC1G265LSEA	LC1G2654BEEA	LC1G2654EHEA	LC1G2654LSEA
440	390	LC1G330BEEA	LC1G330EHEA	LC1G330LSEA	LC1G3304BEEA	LC1G3304EHEA	LC1G3304LSEA
550	490	LC1G400BEEA	LC1G400EHEA	LC1G400LSEA	LC1G4004BEEA	LC1G4004EHEA	LC1G4004LSEA
700	630	LC1G500BEEA	LC1G500EHEA	LC1G500LSEA	LC1G5004BEEA	LC1G5004EHEA	LC1G5004LSEA
1050	850	-	LC1G630EHEA	LC1G630LSEA ⁽²⁾	-	LC1G6304EHEA	LC1G6304LSEA ⁽²⁾
1050	900	-	LC1G800EHEA	LC1G800LSEA ⁽²⁾	-	LC1G8004EHEA	LC1G8004LSEA ⁽²⁾

⁽¹⁾ Switching of IE3/IE4 high efficiency squirrel-cage motors

⁽²⁾ Launch in Q1 2022.

	Motor ratings (HP) UL - 3phase				Reference Advanced version contactors AC/DC coil voltage 3 pole		
	200/208 V	230/240 V	460/480 V	575/600 V	24-48 V ⁽²⁾	48-130 V ⁽²⁾	200-500 V
	30	40	75	100	LC1G115BEEA	LC1G115EHEA	LC1G115LSEA
	40	50	100	125	LC1G150BEEA	LC1G150EHEA	LC1G150LSEA
	50	60	125	150	LC1G185BEEA	LC1G185EHEA	LC1G185LSEA
	60	75	150	150	LC1G225BEEA	LC1G225EHEA	LC1G225LSEA
	75	100	200	200	LC1G265BEEA	LC1G265EHEA	LC1G265LSEA
	100	125	250	300	LC1G330BEEA	LC1G330EHEA	LC1G330LSEA
	125	150	300	400	LC1G400BEEA	LC1G400EHEA	LC1G400LSEA
	150	200	400	450	LC1G500BEEA	LC1G500EHEA	LC1G500LSEA
	250	300	600	700	-	LC1G630EHEA	LC1G630LSEA ⁽²⁾
	300	350	700	800	-	LC1G800EHEA	LC1G800LSEA ⁽²⁾

TeSys Control

Giga Contactors – Standard – 3-pole and 4-pole

Product references

TeSys Giga 3-pole Standard contactors – For motor control – (115 to 800 A)



Motor ratings (kW) $\theta \leq 60^\circ\text{C}$

IEC

AC-3

AC-3e ⁽¹⁾

AC-4

230 V	400 V	415 V	440 V	500 V	690 V	1000 V	230 V	400 V	415 V	440 V	500 V	690 V	1000 V	230 V	400 V	415 V	440 V	500 V	690 V	1000 V
kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW	kW
30	55	55	75	75	75	-	30	55	55	75	75	75	-	30	55	55	65	65	75	-
37	75	75	90	90	90	75	37	75	75	90	90	90	75	37	75	75	80	90	90	75
55	90	90	110	110	110	75	55	90	90	110	110	110	75	55	90	90	100	110	110	75
55	110	110	132	132	132	160	55	110	110	132	132	160	132	55	110	110	129	132	132	110
75	132	132	160	160	160	200	75	132	132	160	160	200	160	75	132	132	150	160	160	160
90	160	160	200	200	220	185	90	160	160	185	200	220	185	90	160	160	185	200	220	185
110	200	200	250	250	315	220	110	200	200	250	250	315	220	110	200	200	220	250	315	220
160	250	250	315	355	355	335	147	250	250	280	315	355	335	150	250	250	295	295	355	280
200	335	375	400	400	500	450	180	315	335	355	375	500	450	180	315	335	355	375	450	355
250	450	450	450	500	560	450	200	335	355	375	425	560	450	200	375	355	375	400	475	400

TeSys Giga 3-pole and 4-pole Standard contactors for load control only (non motor) – (250 to 1050 A / 690 V)



Maximum current (A) ($\theta \leq 40^\circ\text{C}$)	General purpose continuous current (A)	Reference			
IEC AC-1	UL	Standard version contactors			
		AC/DC coil voltage			
		3 Pole		4 Pole	
		48...130 V	100...250 V	48...130 V	100...250 V
250	210	LC1G115EHEN	LC1G115KUEN	LC1G1154EHEN	LC1G1154KUEN
275	230	LC1G150EHEN	LC1G150KUEN	LC1G1504EHEN	LC1G1504KUEN
305	250	LC1G185EHEN	LC1G185KUEN	LC1G1854EHEN	LC1G1854KUEN
330	290	LC1G225EHEN	LC1G225KUEN	LC1G2254EHEN	LC1G2254KUEN
385	340	LC1G265EHEN	LC1G265KUEN	LC1G2654EHEN	LC1G2654KUEN
440	390	LC1G330EHEN	LC1G330KUEN	LC1G3304EHEN	LC1G3304KUEN
550	490	LC1G400EHEN	LC1G400KUEN	LC1G4004EHEN	LC1G4004KUEN
700	630	LC1G500EHEN	LC1G500KUEN	LC1G5004EHEN	LC1G5004KUEN
1050	850	LC1G630EHEN ⁽²⁾	LC1G630KUEN ⁽²⁾	LC1G6304EHEN ⁽²⁾	LC1G6304KUEN ⁽²⁾
1050	900	LC1G800EHEN ⁽²⁾	LC1G800KUEN ⁽²⁾	LC1G8004EHEN ⁽²⁾	LC1G8004KUEN ⁽²⁾

⁽¹⁾ Switching of IE3/IE4 high efficiency squirrel-cage motors

⁽²⁾ Launch in Q1 2022.

TeSys Control

Giga Contactors – Standard – 3-pole and 4-pole


Product references

Motor ratings (HP) UL- 3phase					Reference Standard version contactors AC/DC coil voltage 3 pole	
200/208 V	230/240 V	460/480 V	575/600 V		48-130 V	100-250 V
30	40	75	100		LC1G115EHEN	LC1G115KUEN
40	50	100	125		LC1G150EHEN	LC1G150KUEN
50	60	125	150		LC1G185EHEN	LC1G185KUEN
60	75	150	150		LC1G225EHEN	LC1G225KUEN
75	100	200	200		LC1G265EHEN	LC1G265KUEN
100	125	250	300		LC1G330EHEN	LC1G330KUEN
125	150	300	400		LC1G400EHEN	LC1G400KUEN
150	200	400	450		LC1G500EHEN	LC1G500KUEN
250	300	600	700		LC1G630EHEN ⁽²⁾	LC1G630KUEN ⁽²⁾
300	350	700	800		LC1G800EHEN ⁽²⁾	LC1G800KUEN ⁽²⁾

TeSys Control

Giga Contactors – Auxiliary contact modules

Product references



Auxiliary contact modules

Auxiliary contacts give an indication of the contactor status. They can be used for remote visual signaling, alarming, electrical locking, relay activation, etc...

Each contactor is equipped with 1 NO + 1 NC auxiliary contact block as standard.

■ Mechanically linked mirror contacts

The NC contact of the auxiliary contact block is mirror contact in conformity to IEC 60947-5-1 and it is mechanically linked to reliably represent the state of the main power contacts and wherever auxiliary contact state reliability is essential. The NC of the auxiliary contact can't be closed at the same time as a normally open power contact.

Types of connections:

■ Push-in type.

Wide contactor compatibility

TeSys Giga auxiliary contact module is compatible with the whole range of TeSys Giga Contactors.

Each TeSys Giga Contactor can be equipped with up to 4 auxiliary contact modules.



Electrical characteristics

Characteristics	
Rated thermal current (A)	10
Minimum load	1 mA at 17 V DC
Contact reliability	Failure rate <10 ⁻⁸

Operational power of contacts conforming to IEC 60947-5-1 - Electrical durability

category AC-15

Operating cycles	V	24	48	115	230	400	500
1 million	VA	60	120	280	560	800	500
2 million	VA	24	48	115	230	400	250
3 million	VA	16	32	80	160	280	150



category DC-13

Operating cycles	V	Same current strategy		Same power strategy		
		24	48	125	250	440
0.5 million	W	100	100	105	110	88
1 million	W	48	72	54	54	55
2 million	W	24	36	38	38	39
3 million	W	16	24	25	25	33

Connector characteristics

Push-in connection - Dual input			Min/max c.s.a.
Flexible cable per input	1 conductor with cable end	mm ²	0.75...2.5
	2 conductors with Dual Sleeve	mm ²	0.75...2.5
	Stripping length	mm	10
Solid cable per input	1 conductor	mm ²	0.75...2.5
	Stripping length	mm	12

Auxiliary contact modules

Description	Terminal type	Position	Type of contacts	Sold in lots of	Reference
Auxiliary contact module	Push-in	1 st left or right	1 NO + 1 NC	1	LAG8N113P ⁽¹⁾
			2 NO	1	LAG8N203P
		2 nd left or right	1 NO + 1 NC	1	LAG8N113
			2 NO	1	LAG8N203

⁽¹⁾ Always supplied with TeSys Giga LC1G contactors, fitted to the right side lateral face.



LA9G3601



LA9G3613



LA9G3682



LA9G3631



LA9G3611



LA9G4711

Power terminals

Straight terminal extensions

Description	Suitable for	Compatible with contactors	Sold in lots of	Reference
Straight terminal extension	3P	LC1G115 / LC1G225	3	LA9G3601
		LC1G265 / LC1G500	3	LA9G3602
		LC1G630 / LC1G800	3	LA9G3603
Terminal connections for contactors with larger cables/ busbars	3P	LC1G400 / LC1G500 (50 mm width)	3	LA9G3613
		LC1G630 / LC1G800 (80 mm width)	3	LA9G3614
Straight terminal extension	4P	LC1G115 / LC1G225	4	LA9G4601
		LC1G265 / LC1G500	4	LA9G4602
		LC1G630 / LC1G800	4	LA9G4603
Terminal connections for contactors with larger cables/ busbars	4P	LC1G400 / LC1G500 (50 mm width)	4	LA9G4613
		LC1G630 / LC1G800 (80 mm width)	4	LA9G4614

Right angled terminal extensions


Description	Suitable for	Compatible with contactors	Sold in lots of	Reference
Right angled side terminal extension	3P	LC1G115 / LC1G225	3	LA9G3661
		LC1G265 / LC1G500	3	LA9G3662
		LC1G630 / LC1G800	3	LA9G3663
Right angled large terminal extension	3P	LC1G115 / LC1G225	3	LA9G3671
		LC1G265 / LC1G500	3	LA9G3672
		LC1G630 / LC1G800	3	LA9G3673
Right angled rear terminal extension	3P	LC1G115 / LC1G225	3	LA9G3681
		LC1G265 / LC1G500	3	LA9G3682
		LC1G630 / LC1G800	3	LA9G3683

Edgewise terminal extensions

Description	Suitable for	Compatible with contactors	Sold in lots of	Reference
Edgewise terminal extension	3P	LC1G115 / LC1G225	3	LA9G3631
		LC1G265 / LC1G500	3	LA9G3632
		LC1G630 / LC1G800	3	LA9G3633
Edgewise terminal extension	4P	LC1G115 / LC1G225	4	LA9G4631
		LC1G265 / LC1G500	4	LA9G4632
		LC1G630 / LC1G800	4	LA9G4633

Spreader kits and Terminal adapter for Box connector

Description	Suitable for	Compatible with contactors	Sold in lots of	Reference
Spreader kits	3P	LC1G115 / LC1G225 (35-45 mm)	3	LA9G3611
		LC1G265 / LC1G500 (45-70 mm)	3	LA9G3612
Terminal adapter for contactor with Box connectors	3P	LC1G115 / LC1G225 (35-45 mm)	3	LA9G3711
		LC1G265 / LC1G500 (45-70 mm)	3	LA9G3712
		LC1G630 / LC1G800 (70-80 mm)	3	LA9G3714
Spreader kits	4P	LC1G115 / LC1G225 (35-45 mm)	4	LA9G4611
		LC1G265 / LC1G500 (45-70 mm)	4	LA9G4612
Terminal adapter for contactor with Box connectors	4P	LC1G115 / LC1G225 (35-45 mm)	4	LA9G4711
		LC1G265 / LC1G500 (45-70 mm)	4	LA9G4712
		LC1G630 / LC1G800 (70-80 mm)	4	LA9G4714



LA9G4803



LA9G4701




LA9G4707



LV429252



LA9GQQ330



Power terminal accessories

Phase separators

Description	Suitable for	Compatible with contactors	Sold in lots of	Reference
Phase separators ⁽¹⁾	3P	LC1G115 to LC1G800	4	LA9G3801
	4P	LC1G115 to LC1G800	6	LA9G4801
	3P – with 50/80 mm spreaders	LC1G400 to LC1G800	4	LA9G3803 ⁽²⁾
	4P – with 50/80 mm spreaders	LC1G400 to LC1G800	6	LA9G4803 ⁽³⁾

Terminal shrouds

Description	Compatible with contactors	Reference	
		3P	4P
Terminal shrouds ⁽¹⁾ – IP 20	LC1G115...LC1G225	LA9G3701	LA9G4701
	LC1G265...LC1G500	LA9G3702	LA9G4702
	LC1G630 / LC1G800	LA9G3703	LA9G4703

IP20 Lug cover for coupling assembly

Description	Suitable for	Compatible with contactors	Reference
IP 20 Lug cover for coupling assembly	3P	LC1G115 to LC1G800	LA9G3707
	4P	LC1G115 to LC1G800	LA9G4707

Lugs for cable set

Description	Compatible with contactors	Cable section	Reference	
			Lots of 3 for 3P	Lots of 4 for 4P
Lugs for cable	LC1G115...LC1G225	120 mm ²	LV429252	LV429256
	LC1G115...LC1G225	150 mm ²	LV429253	LV429257
	LC1G115...LC1G225	185 mm ²	LV429254	LV429258
	LC1G265...LC1G500	240 mm ²	LV432500	LV432501
	LC1G265...LC1G500	300 mm ²	LV432502	LV432503

Star-Delta (Wye-Delta) connection kits

Description	Suitable for	for Line /Delta contactor	+ Star contactor	Reference
Connection kit: bars for Line-Delta- Star contactor assembly	3P	LC1G115 / LC1G225	LC1G115 / LC1G225	LA9GQQ330
		LC1G265 / LC1G500	LC1G115 / LC1G225	LA9GSQ330
		LC1G265 / LC1G500	LC1G265 / LC1G500	LA9GSS330
		LC1G630 / LC1G800	LC1G265 / LC1G500	LA9GTS330
		LC1G630 / LC1G800	LC1G630 / LC1G800	LA9GTT330
	with cable memory kit	3P	LC1G265 / LC1G500	LA9GSQ331
			LC1G630 / LC1G800	LA9GTS331

Note: RE17RMMWS timer to be used for Star-Delta starter application.

⁽¹⁾ Either phase separators or terminal shrouds can only be mounted. Phase separators are mandatory for operational voltage, $U_e \geq 690$ V.


⁽²⁾ To be used with LA9G3613 and LA9G3614.

⁽³⁾ To be used with LA9G4613 and LA9G4614.


TeSys Control

Giga Contactors – Power wiring accessories

Product references



LA9G3760





Reverser connection kits

Description	Suitable for	Compatible with contactors	Reference
Connection kit: bars for reverser contactor assembly	3P	LC1G115 / LC1G225	LA9G3760
		LC1G265 / LC1G500	LA9G3761
		LC1G630 / LC1G800	LA9G3762



LA9G3750



Changeover connection kits

Description	Suitable for	Compatible with contactors	Reference
Connection kit: bars for changeover contactor assembly	3P	LC1G115 / LC1G225	LA9G3750
		LC1G265 / LC1G500	LA9G3751
		LC1G630 / LC1G800	LA9G3752
	4P	LC1G115 / LC1G225	LA9G4750
		LC1G265 / LC1G500	LA9G4751
		LC1G630 / LC1G800	LA9G4752



LA9G970

Mechanical interlock

Description	Reference
Mechanical interlock between contactors ⁽¹⁾	Identical contactor frames
	LA9G970
	LC1G265 to 500 and LC1G185 to 225
	LA9G971
	LC1G630 to 800 and LC1G265 to 500
	LA9G972

'Cable Memory' connection block

Cables or busbars can be connected to the contactor by means of the optional cable memory terminal block. When the contactor is removed for maintenance, the cables or busbars remain connected to this terminal block, making reinstallation faster and easier.



LA9G3101

'Cable memory'

Description	Compatible with contactors	Reference For Stand-alone ⁽²⁾	For connect with MCCB ⁽³⁾
'Cable memory' for 3-pole contactors – for holding cables in place when replacing contactor	LC1G115 / LC1G225	LA9G3101	LA9G3111
	LC1G265 / LC1G500	LA9G3102	LA9G3112
	LC1G630 / LC1G800	LA9G3103	LA9G3113
'Cable memory' for 4-pole contactors – for holding cables in place when replacing contactor	LC1G115 / LC1G225	LA9G4101	LA9G4111
	LC1G265 / LC1G500	LA9G4102	LA9G4112
	LC1G630 / LC1G800	LA9G4103	LA9G4113


⁽¹⁾ Maximum 3 auxiliary contacts can be installed between 2 contactors with mechanical interlock kit.

⁽²⁾ 'Cable memory' connection block is always supplied with Advanced contactor version.

⁽³⁾ Launch in Q1 2022.




LA9GRFB1



LA9GRFB2

Retrofit bases

- Suitable for 3 pole contactors
- Retrofit bases to replace similar ratings of TeSys F contactors with TeSys Giga Contactors
- Enables quick and simple replacement in the existing installation
- 2 references to cover ranges from LC1F115 to F500



TeSys Giga retrofit bases are designed for integrating new TeSys Giga Contactors into installations using TeSys F contactors. The retrofit bases help reduce replacement and reinstallation time when you upgrade your system with the new range of contactors. The bases come in two frame sizes.

Retrofit bases		
Description		Reference
Accessory used to replace TeSys F contactors	LC1F115-225 replaced by LC1G115-225	LA9GRFB1
	LC1F265-500 replaced by LC1G265-500	LA9GRFB2
	LC1F630-800 replaced by LC1G630-800	LA9GRFB3 ⁽¹⁾

(1) Launch in Q1 2022.



LX1G3QLSEA



Control module mounted on a 3-pole contactor



LA9G81



LA9GRD10

Control module

Wide band electronic control

24 V...500 V 50/60 Hz or DC control input

Advanced and standard versions

Accessible from the front for easy and quick replacement

The control module is needed for the operation of the contactor.

It performs the following functions:

- proper functioning of contactor based on the input control voltage
- monitoring and diagnostics of the pole condition
- generation of signaling commands.

The range of control modules is organized:

- per contactor size and for each rating,
- per control voltage range.

Each module has connectors for connecting:

- the coil control A1, A2 circuit & PLC output control (advanced version)
- pole status and diagnostic signaling circuits.

Control modules					
Description		For contactors	References per voltage range (V AC/DC)		
			24 - 48 ⁽¹⁾	48 - 130 ⁽¹⁾	200 - 500
Control modules for Advanced contactors	3-pole	LC1G115 / LC1G225	LX1G3QBEEA	LX1G3QEHEA	LX1G3QLSEA
		LC1G265 / LC1G330	LX1G3RBEEA	LX1G3REHEA	LX1G3RLSEA
		LC1G400 / LC1G500	LX1G3SBEEA	LX1G3SEHEA	LX1G3SLSEA
		LC1G630 / LC1G800	-	LX1G3TEHEA	LX1G3TLSEA
	4-pole	LC1G115 / LC1G225	LX1G4QBEEA	LX1G4QEHEA	LX1G4QLSEA
		LC1G265 / LC1G330	LX1G4RBEEA	LX1G4REHEA	LX1G4RLSEA
		LC1G400 / LC1G500	LX1G4SBEEA	LX1G4SEHEA	LX1G4SLSEA
		LC1G630 / LC1G800	-	LX1G4TEHEA	LX1G4TLSEA
			48 - 130	100 - 250	
Control modules for Standard contactors	3-pole	LC1G115 / LC1G225	LX1G3QEHEN	LX1G3QKUEN	
		LC1G265 / LC1G330	LX1G3REHEN	LX1G3RKUEN	
		LC1G400 / LC1G500	LX1G3SEHEN	LX1G3SKUEN	
		LC1G630 / LC1G800	LX1G3TEHEN ⁽¹⁾	LX1G3TKUEN ⁽¹⁾	
	4-pole	LC1G115 / LC1G225	LX1G4QEHEN	LX1G4QKUEN	
		LC1G265 / LC1G330	LX1G4REHEN	LX1G4RKUEN	
		LC1G400 / LC1G500	LX1G4SEHEN	LX1G4SKUEN	
		LC1G630 / LC1G800	LX1G4TEHEN ⁽¹⁾	LX1G4TKUEN ⁽¹⁾	

Connector for control module

Description	Reference
Push-in terminal connector for control module	LA9G81

Remote wear diagnostic (RWD) module

Description	Reference
Remote wear diagnostic module for TeSys Giga Contactor - 1 NO	LA9GRD10 ⁽²⁾
Remote wear diagnostic module for TeSys Giga Contactor - 1 NC	LA9GRD01 ⁽²⁾

⁽¹⁾ Available in Q1 2022.

⁽²⁾ Remote Wear Diagnostic (RWD) Module, can be installed and used only in Advanced version.



Switching module kits

Replaceable switching modules

- Innovative contact switching modules for TeSys Giga Contactors
- Replace worn-out poles with a new switching module in minutes, without having to disassemble the whole product
- No special tools are needed for the replacement.

TeSys Giga - Switching modules for TeSys Giga Contactors, Advanced and Standard versions

Description	For contactors		Reference
3 or 4 switching module kits	3-pole	LC1G115 / LC1G225	LA9G3QA
		LC1G265 / LC1G330	LA9G3RA
		LC1G400 / LC1G500	LA9G3SA
		LC1G630 / LC1G800	LA9G3TA ⁽¹⁾
	4-pole	LC1G115 / LC1G225	LA9G4QA
		LC1G265 / LC1G330	LA9G4RA
		LC1G400 / LC1G500	LA9G4SA
		LC1G630 / LC1G800	LA9G4TA ⁽¹⁾

Note: In the event of replacement, replace all switching modules. After replacement, change the position of RESET button on the control module from A to B or B to A.

⁽¹⁾ Available in Q1 2022.

Technical Data for Designers

Contents




TeSys Giga Contactors:

> Characteristics	25 to 29
> Dimensions	30 to 32
> Diagrams	33

TeSys Control

Giga Contactors

Characteristics

Environment						
Contactor type				LC1G115... 225	LC1G265... 500	LC1G630... 800 ⁽¹⁾
Rated insulation voltage (Ui)	Conforming to IEC 60947-4-1. Overvoltage category III, degree of pollution: 3		V	1000	1000	1000
Rated impulse withstand voltage (Uimp)	Coil not connected to the power circuit		kV	8	8	8
Conforming to standards				IEC/EN 60947-4-1, UL 60947-4-1, CSA C22.2 n° 60947-4-1, JIS C 8201-4-1, GB 14048.4, IEC 60721-3-3 3C3		
Product certifications				cULus , CCC, CB certification, UKCA EAC, ABS, BV, DNV-GL, LRoS, RINA, RMRoS ⁽²⁾		
Electromagnetic compatibility				IEC 60947-4-1		
Imunity				Following IEC 60947-4-1 Table 14		
Emission				Environnement A According to IEC 60947-4-1		
Immunity to radiated electromagnetic interference				20V/m according to IEC/EN 61000-4-3		
Voltage sag immunity (in complete product as well)				Conforming to SEMI-F47		
Degree of protection	Conforming to IEC 60529 / VDE 0106			IP2x with terminal shrouds LA9G37●●/ LA9G47●●		
Climatic withstand				According to IACS E10		
Ambient air temperature around the device	Storage		°C	-60...+80		
	Operation		°C	-25...+60		
	Permissible at Uc		°C	-40...+70		
Net weight	Standard	3P	kg	4.6	8.7	-
		4P	kg	6.1	10.7	-
	Advanced	3P	kg	5.4	8.7	-
		4P	kg	6.1	10.7	-
Maximum operating altitude	Without derating		m	3000		
Operating positions	Without derating					
	With derating					
Shock resistance 1/2 sine wave = 11 ms Conforming to IEC 60068-2-7	Contactor open			10 gn	10 gn	8 gn
	Contactor closed			15 gn	15 gn	15 gn
Vibration resistance 5...300 Hz Conforming to IEC 60068-2-6	Contactor open			2 gn	2 gn	2 gn
	Contactor closed			4 gn	4 gn	4 gn

⁽¹⁾ Launch in Q1 2022.

⁽²⁾ EAC, ABS, BV, DNV-GL, LRoS, RINA, RMRoS: Certifications in progress and shall be available in H2 2021.

TeSys Control

Giga Contactors

Characteristics

Pole characteristics						
Contactor type			LC1G115	LC1G150	LC1G185	LC1G225
Number of poles			3 or 4	3 or 4	3 or 4	3 or 4
Rated operational current (Ie) (Ue ≤ 440 V)	In AC-3 / AC-3e ≤ 60 °C	A	115 / 115	150 / 145	185 / 177	225 / 209
	In AC-1, θ ≤ 40 °C	A	250	275	305	330
Rated operational voltage (Ue)	Up to	V	1000 ⁽¹⁾	1000 ⁽¹⁾	1000 ⁽¹⁾	1000 ⁽¹⁾
Rated frequency (f) ⁽²⁾		Hz	50 / 60	50 / 60	50 / 60	50 / 60
Frequency operating limits	With derating	Hz	16 ^{2/3} ...400	16 ^{2/3} ...400	16 ^{2/3} ...400	16 ^{2/3} ...400
Conventional thermal current	θ ≤ 40 °C	A	250	275	305	330
Rated making capacity	I rms conforming to IEC 60947-4-1	A	Making current: 10 x I in AC-3 or 12 x I in AC-4 Making current: 13 x I in AC-3e			
Rated breaking capacity	I rms conforming to IEC 60947-4-1	A	Making and breaking current: 8 x I in AC-3 or 10 x I in AC-4 Making and breaking current: 8.5 x I in AC-3e			
Maximum permissible current No current flowing for previous 60 minutes, at θ ≤ 40 °C	For 10 s	A	1100	1200	1500	1800
	For 30 s	A	640	700	920	1000
	For 1 min	A	520	600	740	850
	For 3 min	A	400	450	500	560
	For 10 min	A	320	350	400	440
Short-circuit protection by fuses	Fuses for motor: type aM - Ue ≤ 440 V	A	125	160	200	250
	Fuses for motor: type aM - Ue ≤ 690 V	A	125	160	160	200
	Fuses for general application: type gL - Ue ≤ 690 V	A	315	315	315	400
Average impedance per pole	At Ith and 50 Hz	mΩ	0.18	0.18	0.17	0.15
Power dissipation per pole for the above operational currents	AC-3 / AC-3e	W	3	5	6	8
	AC-1	W	10	10	20	20
Connection	Bar	Number of bars	Maximum c.s.a.			
	Bar		2	2	2	2
	Cable with lug	mm	25 x 6	25 x 6	25 x 6	25 x 6
	Cable with connector	mm²	185	185	185	185
	Bolt diameter	mm	Ø8.5	Ø8.5	Ø8.5	Ø8.5
Tightening torque	Power circuit connections	N.m	18	18	18	18

(1) Ue = 1000 V Simple Insulation / Ue = 690 V SELV.

(2) Please consult your technical support team for application with frequencies other than 50/60 Hz.

TeSys Control

Giga Contactors

Characteristics

Pole characteristics					
LC1G265	LC1G330	LC1G400	LC1G500	LC1G630 ⁽²⁾	LC1G800 ⁽²⁾
3 or 4	3 or 4	3 or 4	3 or 4	3 or 4	3 or 4
265 / 255	330 / 294	400 / 391	500 / 437	630 / 555	800 / 587
385	440	550	700	1050	1050
1000 ⁽¹⁾	1000 ⁽¹⁾	1000 ⁽¹⁾	1000 ⁽¹⁾	1000 ⁽¹⁾	1000 ⁽¹⁾
50 / 60	50 / 60	50 / 60	50 / 60	50 / 60	50 / 60
16 ^{2/3} ...400	16 ^{2/3} ...400	16 ^{2/3} ...400	16 ^{2/3} ...400	16 ^{2/3} ...400	16 ^{2/3} ...400
385	440	550	700	1050	1050
Making current: 10 x I in AC-3 or 12 x I in AC-4					
Making current: 13 x I in AC-3e					
Making and breaking current: 8 x I in AC-3 or 10 x I in AC-4					
Making and breaking current: 8.5 x I in AC-3e					
2200	2650	3600	4000	5050	5500
1230	1800	2400	2800	4400	4600
950	1300	1700	2200	3400	3600
620	900	1200	1500	2200	2600
480	750	1000	1200	1600	1700
315	400	500	500	630	800
250	250	315	400	500	630
400	500	630	800	1250	1250
0.144	0.144	0.1	0.08	0.065	0.065
11	16	16	20	26	42
20	30	30	40	70	70
Maximum c.s.a.					
2	2	2	2	2	2
32 x 10	32 x 10	32 x 10	32 x 10	52 x 20	52 x 20
240	2 x 150	2 x 185	2 x 240	300	300
240	-	-	-	-	-
Ø10.6	Ø10.6	Ø10.6	Ø10.6	Ø13	Ø13
35	35	35	35	58	58

⁽¹⁾ Ue = 1000 V Simple Insulation / Ue = 690 V SELV.

⁽²⁾ Launch in Q1 2022.

TeSys Control

Giga Contactors

Characteristics

TeSys Giga contactors - Advanced version - Control circuit characteristics with AC/DC coils									
Contactor type					LC1G115...225	LC1G265...330	LC1G400...500	LC1G630...800 ⁽¹⁾	
Rated control circuit voltage (Uc)				V	24...48 AC/DC, 48...130 AC/DC, 200...500 AC/DC				
Control voltage limits (θ ≤ 60 °C)	50/60 Hz coils	Operation			0.8 Uc Min...1.1 Uc Max				
		Drop-out			≤ 0.45 Uc Min				
Inputs compatibility PLC digital output 24 V DC Type 3 IEC61131-2		Off-state		V DC	0...5				
		On-state		V DC	11...30				
Average consumption at 20 °C and at Uc (3 and 4-pole contactors)	24...48 V AC/DC coil (BEE)	Inrush	50/60 Hz coil	VA	308	520	490	-	
			DC	W	220	350	317	-	
		Sealed	50/60 Hz coil	VA	8.9	17.9	15.8	-	
			DC	W	5.7	6.4	6	-	
	48...130 V AC/DC coil (EHE)	Inrush	50/60 Hz coil	VA	225	430	450	560	
			DC	W	180	310	305	330	
		Sealed	50/60 Hz coil	VA	7.1	12.7	12.6	14.6	
			DC	W	3	9	8.3	8.8	
	200...500 V AC/DC coil (LSE)	Inrush	50/60 Hz coil	VA	295	531	533	672	
			DC	W	216	303	300	392	
		Sealed	50/60 Hz coil	VA	13	16.1	15.4	18.4	
			DC	W	8	9	8.6	11	
Heat dissipation				W	4...5	5...6	5...6	5...6	
Operating time	Closing "C"			ms	40...70	40...70	40...70	40...70	
	Opening "O"			ms	15...50	15...50	15...50	15...50	
Mechanical durability at Uc	In millions of operating cycles (max)				8	8	8	5	
Maximum operating rate at ambient temperature ≤ 60 °C	In operating cycles per hour	AC-1			300	300	300	300	
		AC-3			500	500	500	500	
		AC-4			150	150	60	60	
Coil control and PLC input connection (Push-in type)					Min/max c.s.a.				
Flexible cable	1 conductor with cable end		mm²		0.25...2.5	0.25...2.5	0.25...2.5	0.25...2.5	
	2 conductors with Dual Sleeve		mm²		0.5...1	0.5...1	0.5...1	0.5...1	
Solid cable	1 conductor		mm²		0.2...2.5	0.2...2.5	0.2...2.5	0.2...2.5	
	Stripping length		mm		12	12	12	12	

⁽¹⁾ Launch in Q1 2022.

TeSys Control

Giga Contactors

Characteristics

TeSys Giga Contactors - Standard version control circuit characteristics with AC/DC coils									
Contactor type					LC1G115...225	LC1G265...330	LC1G400...500	LC1G630...800 ⁽¹⁾	
Rated control circuit voltage (Uc)				V	48...130 AC/DC, 100...250 AC/DC				
Control voltage limits (θ ≤ 60 °C)	50/60 Hz coils	Operation			0.8 Uc Min...1.1 Uc Max				
		Drop-out			≤ 0.45 Uc Min				
Average consumption at 20 °C and at Uc (3 and 4-pole contactors)	48...130 V AC/DC coil (EHE)	Inrush	50/60 Hz coil	VA	640	778	963	990	
			DC	W	445	695	760	850	
		Sealed	50/60 Hz coil	VA	18.7	17.6	17.6	21.6	
			DC	W	7.8	7.8	7.8	9.5	
	100...250 V AC/DC coil (KUE)	Inrush	50/60 Hz coil	VA	540	698	750	798	
			DC	W	380	645	690	710	
		Sealed	50/60 Hz coil	VA	12.4	15	15.5	16.9	
			DC	W	7.8	9.1	9.3	9.5	
Heat dissipation				W	5...6	6...7	6...7	6...7	
Operating time	Closing "C"			ms	40...70	40...70	40...70	40...70	
	Opening "O"			ms	15...50	15...50	15...50	15...50	
Mechanical durability at Uc	In millions of operating cycles (max)				8	8	8	5	
Maximum operating rate at ambient temperature ≤ 60 °C	In operating cycles per hour	AC-1			300	300	300	300	
		AC-3			500	500	500	500	
		AC-4			150	150	60	60	
Coil control connection (Push-in type)					Min/max c.s.a.				
Flexible cable	1 conductor with cable end			mm ² 	0.25...2.5	0.25...2.5	0.25...2.5	0.25...2.5	
	2 conductors with Dual Sleeve			mm ² 	0.5...1	0.5...1	0.5...1	0.5...1	
Solid cable	1 conductor			mm ² 	0.2...2.5	0.2...2.5	0.2...2.5	0.2...2.5	
	Stripping length			mm 	12	12	12	12	

⁽¹⁾ Launch in Q1 2022.


TeSys Control

Giga Contactors

Dimensions

Advanced LC1G115...225 TeSys Giga Contactors

3-pole



a	b	c	G	J	M	H	L	P	Q	S	Ø
108	255	193	35	166	226	145	67	35	19	18	8.5

X1 (mm) = Minimum electrical clearance.


LC1G115...800, up to 1000 V: 40 mm

X2 (mm) = Minimum electrical clearance according to operating voltage inside metallic cabinets.

LC1G115...800, up to 600 V: 5 mm

a' = a + 20 mm with additional auxiliary contact blocks on both sides (externally).


4-pole



a	b	c	G	J	M	H	L	P	Q	S	Ø
143	255	193	70	166	226	145	67	35	19	18	8.5

Standard LC1G115...225 TeSys Giga Contactors

3-pole



a	b	c	G	J	M	H	L	P	Q	S	Ø
108	193	193	35	166	164	145	70	35	19	18	8.5

X1 (mm) = Minimum electrical clearance.


LC1G115...800, up to 1000 V: 40 mm

X2 (mm) = Minimum electrical clearance according to operating voltage inside metallic cabinets.

LC1G115...800, up to 600 V: 5 mm

a' = a + 20 mm with additional auxiliary contact blocks on both sides (externally).

4-pole



a	b	c	G	J	M	H	L	P	Q	S	Ø
143	193	193	70	166	164	145	70	35	19	18	8.5


TeSys Control

Giga Contactors

Dimensions

Advanced LC1G265...500 TeSys Giga Contactors

3-pole



	a	b	c	G	J	M	H	L	P	Q	S	Ø
265-330	140	290	225	45	187	262	167	79	45	25	30	10.6
400	140	290	225	45	187	262	167	79	45	25	30	10.6
500	140	290	225	45	187	262	167	79	45	25	30	10.6

X1 (mm) = Minimum electrical clearance.


LC1G115...800, up to 1000 V: 40 mm.

X2 (mm) = Minimum electrical clearance according to operating voltage inside metallic cabinets.

LC1G115...800, up to 600 V: 5 mm

a' = a + 20 mm with additional auxiliary contact blocks on both sides (externally).


4-pole



	a	b	c	G	J	M	H	L	P	Q	S	Ø
265-330	185	290	225	90	187	262	167	82	45	25	30	10.6
400	185	290	225	90	187	262	167	83	45	25	30	10.6
500	185	290	225	90	187	262	167	84	45	25	30	10.6

Standard LC1G265...500 TeSys Giga Contactors

3-pole



	a	b	c	G	J	M	H	L	P	Q	S	Ø
265-330	140	225	225	45	187	197	167	82	45	25	30	10.6
400	140	225	225	45	187	197	167	83	45	25	30	10.6
500	140	225	225	45	187	197	167	84	45	25	30	10.6

X1 (mm) = Minimum electrical clearance.


LC1G115...800, up to 1000 V: 40 mm.

X2 (mm) = Minimum electrical clearance according to operating voltage inside metallic cabinets.

LC1G115...800, up to 600 V: 5 mm

a' = a + 20 mm with additional auxiliary contact blocks on both sides (externally).

4-pole



	a	b	c	G	J	M	H	L	P	Q	S	Ø
265-330	185	225	225	90	187	197	167	82	45	25	30	10.6
400	185	225	225	90	187	197	167	83	45	25	30	10.6
500	185	225	225	90	187	197	167	84	45	25	30	10.6

TeSys Control


Retrofit base plates to replace **TeSys F** contactors

Dimensions/mounting

Dimensions


LA9GRBF1

For replacement of F115-225



LGRBF2

For replacement of F265-500




TeSys Control

Giga Contactors


Diagrams

TeSys Giga Contactors


Advanced version - ON/OFF control by PLC




Advanced version - ON/OFF control by PLC in safety application



Advanced version - Control by switch



Standard version




Add-on blocks

Instantaneous auxiliary contacts


1 N/O + 1 N/C

LAG8N113P
mirror contacts




2 N/O

LAG8N203P



1 N/O + 1 N/C

LAG8N113
mirror contacts



2 N/O

LAG8N203



(1) Terminal numbers in brackets refer to blocks when mounted upside down, on left-hand side of contactor.

TeSys Protect

Giga Electronic Overload Relays



TeSys Giga Electronic Overload Relays			
Type of product	Range		Pages
Introduction			36
Overload relays for TeSys Giga Contactors TeSys Giga Electronic Overload Relays	From 28 to 630 A		38
Accessories TeSys Giga Electronic Overload Relays			38
Technical Data for Designers			39

TeSys Protect

Giga Electronic Overload Relays

Introduction

> Intelligent design for greater advantages



TeSys Protect

Giga Electronic Overload Relays

Description

Range

- A comprehensive range of TeSys Giga Electronic Overload Relays in 3 sizes
- Direct mounting of relay with contactors saving in panel space and installation time



28...115 A and 57...225 A



125...500 A

Overload relays

- Advanced electronic monitoring with high accuracy
- Thermal compensation for ambient temperatures up to 60 °C
- Wide range of current settings, 0.25...1 I_r setting
- Direct and separately mountable to manage panel design
- Pole pitch alignment with contactors, enabling direct mounting
- Push-in terminals for quick and easy control wiring options
- 4 references covering the complete range means less inventory
- Manual and auto reset to suit your needs
- Multiple reset options: Manual, Automatic & Remote
- Protection against phase loss
- Selectable protection against imbalanced load
- Selectable protection against ground fault
- ON status and overload alarm signaling by LED
- TRIP indicator

Certifications

- Multiple standards
- International certifications

Trip class

- Selectable, from class 5E to class 30E to suit different application needs

> Perfect selection for your motor protection

TeSys Protect

Giga Electronic Overload Relays

Product references



LR9G225



Direct mounting
with TeSys Giga Contactor



LA9G3650



LA9G82



LA9G3704



LAD7305

TeSys Giga Electronic Overload Relays

- Electronic overload relay
- Suitable for independent mounting or direct mounting with TeSys Giga contactors
- Ergonomic rotary switches for thermal and protection settings
- Trip class selection: 5E/10E/20E/30E
- Overload, phase imbalance, phase loss and ground fault protections
- Manual and auto reset options
- LED indicator for Motor ON and pre-trip alarm
- Thermal memory and compensation
- Push-in terminals for control connections

Relay setting range	Fuses to be used with selected relay		For direct mounting beneath contactor LC1G	Reference
	aM /gG/aR	kA		
A	A			
Class 5...30 A				
28...115	125 aM	100	LC1G115...225	LR9G115
57...225	250 aM	100	LC1G115...225	LR9G225
125...500	630 aM	100	LC1G265...500	LR9G500
	630 gG	80		
	630 aR	25		
160...630	800 aR	100	LC1G630	LR9G630 ⁽¹⁾
	800 aR	80		
	800 aR	25		

⁽¹⁾ Launch in Q1 2022.

Overload Relay accessories

Mounting and wiring accessories

Description	Reference
Mounting base for alignment of LR9G115-225 with LC1G115-225 ⁽²⁾	LA9G3650
Mounting base for alignment of LR9G500 with LC1G265-330 ⁽²⁾	LA9G3651
Mounting base for alignment of LR9G500 with LC1G400-500 ⁽²⁾	LA9G3652
Mounting base for alignment of LR9G630 with LC1G630-800 ⁽²⁾	LA9G3653
Push-in connection adapter	LA9G82

Front protection cover

Description	Compatible with contactors	Reference
Front protection cover ⁽³⁾	LR9G115 / LR9G225	LA9G3704
	LR9G500	LA9G3705
	LR9G630	LA9G3706

⁽²⁾ Used for independent mounting of Overload Relay beneath contactor to align main power pole connections.

⁽³⁾ Used to cover main power connection terminals between contactor and overload with direct mounting option.

Remote Reset control device

Description	Sold in lots of	Reference
Remote Reset function control by flexible cable (length = 0.5 m)	1	LAD7305

Technical Data for Designers

Contents

TeSys Giga Electronic Overload Relays:

- > Characteristics..... 40 to 42
- > Dimensions, diagram 43

TeSys Protect

Giga Electronic Overload Relays

Characteristics

Environment					
Contactor type		LR9G115	LR9G225	LR9G500	LR9G630
Conforming to standards			IEC/EN 60947-4-1, IEC/EN 60947-5-1, UL 60947-4-1, CSA C22.2 n° 60947-4-1, UL 60947-5-1, CSA C22.2 n° 60947-5-1, GB/T 14048.4		
Product certifications			UL, CSA, CCC, ABS, BV, DNV-GL, UKCA		
Degree of protection	Conforming to IEC 60529 / VDE 0106		IP 20 on front of relay with accessories LA9G37●●		
Climatic withstand			according to IACS E10		
Ambient air temperature around the device (conforming to IEC 60255-8)	Storage	°C	-55...+80		
	Normal operation	°C	-25...+60		
Maximum operating altitude	Without derating	m	3000		
Net weight		kg	1.2	1.7	-
Operating positions without derating	In relation to normal vertical mounting plane		Any position		
Shock resistance 11 ms	Permissible acceleration conforming to IEC 60068-2-7		15 gn		
Vibration resistance 5 to 300 Hz	Permissible acceleration conforming to IEC 60068-2-6		6 gn		
Rated impulse withstand voltage (Uimp)	Conforming to IEC 60947-4-1	kV	8		
Surge withstand	Conforming to IEC 61000-4-5	kV	4		
Resistance to electrostatic discharge	Conforming to IEC 61000-4-2	kV	8 (in air) 6 (in direct mode)		
Resistance to radiated radio-frequency disturbance	Conforming to IEC 61000-4-3	V/m	20		
Resistance to fast transient currents	Conforming to IEC 61000-4-4	kV	4		
Electromagnetic compatibility	EN 50081-1 and 2, EN 50082-2		Conforming		

TeSys Protect

Giga Electronic Overload Relays

Characteristics

Power circuit - Electrical characteristics						
Relay type			LR9G115	LR9G225	LR9G500	LR9G630
Rated insulation voltage (Ui)	Conforming to IEC 60947-4-1 Overvoltage category III, degree of pollution: 3	V	1000			
Rated impulse withstand voltage (Uimp)	Conforming to IEC 60947-1	kV	8			
Rated operational current (Ie)		A	28 to 630			
Short-circuit protection and coordination			See pages 50 to 53 and 58 to 60			
Frequency limits of the operating current		Hz	50 / 60			
Power circuit connections	Width of terminal lug	mm	18	18	30	48
	Clamping screw		M8	M8	M10	M12
	Tightening torque	N.m	18	18	35	58

Auxiliary contact electrical characteristics									
Conventional thermal current		A	5						
Short-circuit protection	By gG fuses	A	6						
Connection (Push-in type)			Min.	Max.					
Flexible cable	1 conductor with cable end	mm ² 	0.25	2.5					
	2 conductors with Dual Sleeve	mm ² 	0.5	1					
Solid cable	1 conductor	mm ² 	0.2	2.5					
	Stripping length	mm 	10	10					
Rated operational contact power	a.c. supply AC-15	V	24	48	120	240	380	480	500
		A	4	4	3	1.5	0.95	0.75	0.72
		VA	96	192	360	360	361	360	360
	d.c. supply DC-13	V	24	48	125	250	–	–	–
		A	2	0.7	0.22	0.11	–	–	–
		W	48	33.6	27.5	27.5	–	–	–
Maximum operational voltage	a.c., category AC-15	V	500	500	500	500	500	500	500
	d.c., category DC-13	V	250	250	250	250	250	250	250

TeSys Protect

Giga Electronic Overload Relays

Characteristics


Operating characteristics

Tripping class	Conforming to IEC 60947-4-1		5E/10E/20E/30E
Temperature compensation		°C	-40...+60
Reset			auto and manual
Trip alarm and fault indication			On front of relay
Test function			On front of relay
Tripping thresholds	Conforming to IEC 60947-4-1	Alarm	≥ 90% of permissible thermal state
		Tripping	A $1.2 \pm 0.05 I_r$
Sensitivity to phase loss	Conforming to IEC 60947-4-1		Tripping in $4 \text{ s} \pm 20 \%$ in the event of phase loss
Phase imbalance	Conforming to IEC 60947-1		Tripping in $5 \text{ s} \pm 20 \%$ if imbalance ratio ≥ 40 % according to Annex T5.5
Ground fault	Conforming to IEC 60947-4-1		$I_g = 0.75 I_r$ Tripping $1 \text{ s} \pm 20 \%$ if $I \geq 1.1 I_g$
Adjustment (nominal motor current)			Setting dial on front of relay (64 settings)
Security sealing			Yes

LR9G tripping curves


Average operating times depending on multiples of the setting current

Class 5E




- 1 Hot state
- 2 Cold state

Class 20E




- 1 Hot state
- 2 Cold state

Class 10E



- 1 Hot state
- 2 Cold state

Class 30E



- 1 Hot state
- 2 Cold state

TeSys Protect



Giga Electronic Overload Relays

Dimensions and diagram


Dimensions

LR9G115...630

DB438399.ai




DB439402.ai



LR9G	115-225	500	630
a	105.7	140	210
b	109.55	115.65	149.45
c	126.2	139.2	185.9
G1	70	119.3	186.2
G2	35	45	70
J	80.1	68.25	87
M	78	83	100
H	52	47	47
L	66	79	107
P	35	45	70
Q	18	25	35
S1	11.5	22.5	22.5
S2	17.5	30.5	50
Ø1	8.3	10.6	13
Ø2	9	10.6	13
Ø3	5.3	5.3	8.5
X1	30	33	50

Diagram

DB439512.ai



Coordination tables

Content	Pages
Coordination for D.O.L. / Reverser motor starters	46
Optimized solutions for Star-Delta motor starters	55
Star-Delta motor starter - Common circuit diagrams	61
Resistive load protection and control	62

TeSys Giga Contactors for various applications

Utilisation category AC-3	64
Utilisation category AC-1	66
Utilisation category AC-2 or AC-4	67
Utilisation category DC-1 to DC-5	69
Heating	70
Power factor correction	72

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Thermal magnetic circuit breakers + Contactors

45 to 250 kW at 400 V: type 2 coordination (with ref. GV4, GV5, GV6 circuit breakers)						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
400 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
45	80	100	GV4P/GV4PE/GV4PEM115●	86	1118	LC1G115
55	97	100	GV4P115●	100	1300	LC1G115
55	97	70	GV5P150●	100	1300	LC1G115
75	132	70	GV5P150●	140	1820	LC1G150
90	160	70	GV5P220●	170	2210	LC1G185
110	195	70	GV5P220●	200	2600	LC1G225
110	195	70	GV6P320●	200	2600	LC1G265
132	230	70	GV6P320●	240	3120	LC1G265
160	280	70	GV6P320●	300	3900	LC1G330
200	350	70	GV6P500●	380	4940	LC1G400
220	380	70	GV6P500●	400	5200	LC1G500
250	430	70	GV6P500●	440	5720	LC1G500

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV4P/GV4PE/GV4PEM115●			GV5P150●/ 220● GV6P320●/ 500●		
Code	B	N	S	F	H	
400 V	25	50	100	36	70	

45 to 450 kW at 400 V: type 2 coordination (with NSX circuit breakers)						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
400 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
45	80	130	NSX100● + Micrologic 2.2M	85	1105	LC1G115
55	97	130	NSX160● + Micrologic 2.2M ⁽²⁾	100	1300	LC1G115
75	132	130	NSX160● + Micrologic 2.2M ⁽²⁾	140	1820	LC1G150
90	160	130	NSX250● + Micrologic 2.2M ⁽²⁾	170	2210	LC1G185
110	195	130	NSX250● + Micrologic 2.2M ⁽²⁾	200	2600	LC1G225
110	195	130	NSX400● + Micrologic 2.3M ⁽²⁾	200	2600	LC1G265
132	230	130	NSX400● + Micrologic 2.3M ⁽²⁾	240	3120	LC1G265
160	280	130	NSX400● + Micrologic 2.3M ⁽²⁾	300	3900	LC1G330
200	350	130	NSX630● + Micrologic 2.3M ⁽²⁾	380	4940	LC1G400
220	380	130	NSX630● + Micrologic 2.3M ⁽²⁾	400	5200	LC1G500
250	430	130	NSX630● + Micrologic 2.3M ⁽²⁾	440	5720	LC1G500
300	460	130	NS800● + Micrologic 5	470	6110	LC1G630
335	575	130	NS800● + Micrologic 5	640	8320	LC1G630
355	610	130	NS800● + Micrologic 5	640	8320	LC1G800
400	690	130	NS800● + Micrologic 5	720	9360	LC1G800
450	770	130	NS1000● + Micrologic 5	784	10192	LC1G800

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX100●/ NSX160●/ NSX250●/ NSX400●/ NSX630●				NS800●/ NS1000●		
Code	F	N	H	R	N	H	L
400 V	36	50	70	200	50	70	150

⁽²⁾ Contact technical support for compatibility with other types of trip units.

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Thermal magnetic circuit breakers + Contactors

55 to 300 kW at 440 V: type 2 coordination (with ref. GV4, GV5, GV6 circuit breakers)						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
440 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
55	88	100	GV4P/GV4PE/GV4PEM115●	93	1209	LC1G115
55	88	70	GV5P150●	90	1170	LC1G115
75	120	70	GV5P150●	130	1690	LC1G150
90	145	70	GV5P150●	150	1950	LC1G150
110	177	70	GV5P220●	185	2405	LC1G185
132	209	70	GV5P220●	210	2730	LC1G225
160	255	70	GV6P320●	260	3380	LC1G265
200	318	70	GV6P320●	320	4160	LC1G330
220	343	70	GV6P500●	350	4550	LC1G400
250	390	70	GV6P500●	400	5200	LC1G400
300	466	70	GV6P500●	470	6580	LC1G500

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV4P/GV4PE/GV4PEM115●			GV5P150●/ 220● GV6P320●/ 500●		
Code	B	N	S	F	H	
440 V	25	50	100	36	70	

55 to 450 kW at 440 V: type 2 coordination (with ref. NSX circuit breakers)						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
440 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
55	88	130	NSX100● + Micrologic 2.2M	90	1170	LC1G115
75	120	130	NSX160● + Micrologic 2.2M ⁽²⁾	130	1690	LC1G150
90	145	130	NSX160● + Micrologic 2.2M ⁽²⁾	150	1950	LC1G150
110	177	130	NSX250● + Micrologic 2.2M ⁽²⁾	185	2405	LC1G185
132	209	130	NSX250● + Micrologic 2.2M ⁽²⁾	210	2730	LC1G225
160	255	130	NSX400● + Micrologic 2.3M ⁽²⁾	260	3380	LC1G265
200	318	130	NSX400● + Micrologic 2.3M ⁽²⁾	320	4160	LC1G330
220	343	130	NSX630● + Micrologic 2.3M ⁽²⁾	350	4550	LC1G400
250	390	130	NSX630● + Micrologic 2.3M ⁽²⁾	400	5200	LC1G400
300	466	130	NSX630● + Micrologic 2.3M ⁽²⁾	470	6110	LC1G500
335	521	130	NS800● + Micrologic 5	560	7280	LC1G630
355	554	130	NS800● + Micrologic 5	560	7280	LC1G630
400	627	130	NS800● + Micrologic 5	640	8320	LC1G800
450	695	130	NS800● + Micrologic 5	720	9360	LC1G800

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX100●/ NSX160●/ NSX250●				NSX400●/ NSX630●				NS800●			
Code	F	N	H	R	F	N	H	R	N	H	L	
440 V	35	50	65	200	30	42	65	200	50	65	130	

⁽²⁾ Contact technical support for compatibility with other types of trip units.

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Thermal magnetic circuit breakers + Contactors

65 to 295 kW at 500 V: type 2 coordination (with ref. GV4P, GV5P, GV6P circuit breakers)						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
500 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
65	92	30	GV4P/GV4PE/GV4PEM115●	93	1209	LC1G115
65	92	50	GV5P150●	100	1300	LC1G115
90	128	50	GV5P150●	130	1690	LC1G150
110	156	50	GV5P220●	170	2210	LC1G185
132	184	50	GV5P220●	185	2405	LC1G225
160	224	50	GV6P320●	240	3120	LC1G265
200	280	50	GV6P320●	300	3900	LC1G330
250	344	50	GV6P500●	350	4550	LC1G400
295	405	50	GV6P500●	440	5720	LC1G500

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV4P/GV4PE/GV4PEM115●			GV5P150●/ 220● GV6P320●/ 500●		
Code	B	N	S	F	H	
500 V	10	25	30	30	50	

65 to 425 kW at 500 V: type 2 coordination (with NSX circuit breakers)						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
500 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
65	92	70	NSX100● + Micrologic 2.2M	95	1235	LC1G115
65	92	70	NSX160● + Micrologic 2.2M ⁽²⁾	95	1235	LC1G115
90	128	70	NSX160● + Micrologic 2.2M ⁽²⁾	130	1690	LC1G150
110	156	70	NSX250● + Micrologic 2.2M ⁽²⁾	170	2210	LC1G185
132	184	70	NSX250● + Micrologic 2.2M ⁽²⁾	185	2405	LC1G225
160	224	70	NSX400● + Micrologic 2.3M ⁽²⁾	240	3120	LC1G265
200	280	70	NSX400● + Micrologic 2.3M ⁽²⁾	300	3900	LC1G330
250	344	70	NSX630● + Micrologic 2.3M ⁽²⁾	350	4550	LC1G400
295	405	70	NSX630● + Micrologic 2.3M ⁽²⁾	440	5720	LC1G500
375	516	70	NS800● + Micrologic 5	560	7280	LC1G630
425	584	70	NS800● + Micrologic 5	640	8320	LC1G800

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX100●				NSX160●/ NSX250●				NSX400●/ NSX630●				NS800●			
Code	F	N	H	R	F	N	H	R	F	N	H	R	N	H	L	
500 V	25	36	50	80	30	36	50	80	25	30	50	80	40	50	100	

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Thermal magnetic circuit breakers + Contactors

30 to 560 kW at 690 V: type 2 coordination						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker			Contactor
690 V			Reference ⁽¹⁾	Ir Setting	Irm	Reference
P	Ie	Iq (max)				
kW	A	kA		A	A	
30	32	100	NSX100● + Micrologic 2.2 M	36	468	LC1G115
37	39	100	NSX100● + Micrologic 2.2 M	40	520	LC1G115
45	47	100	NSX100● + Micrologic 2.2 M	50	650	LC1G115
55	57	100	NSX100● + Micrologic 2.2 M	60	780	LC1G115
75	77	100	NSX100● + Micrologic 2.2 M	80	1040	LC1G115
90	93	100	NSX250● + Micrologic 2.2 M	95	1235	LC1G150
110	113	100	NSX250● + Micrologic 2.2 M	115	1495	LC1G185
132	134	100	NSX250● + Micrologic 2.2 M	140	1820	LC1G225
160	162	100	NSX250● + Micrologic 2.2 M	170	2210	LC1G225
200	203	100	NSX250● + Micrologic 2.2 M	210	2730	LC1G265
220	223	100	NSX400● + Micrologic 2.3M	240	3120	LC1G330
250	250	100	NSX400● + Micrologic 2.3M	260	3380	LC1G400
315	313	100	NSX630● + Micrologic 2.3M	320	4160	LC1G400
335	335	100	NSX630● + Micrologic 2.3M	350	4550	LC1G500
355	354	100	NSX630● + Micrologic 2.3M	380	4940	LC1G500
375	374	100	NSX630● + Micrologic 2.3M	380	4940	LC1G630
400	400	100	NSX630● + Micrologic 2.3M	440	5720	LC1G630
450	455	100	NSX630● + Micrologic 2.3M	470	6110	LC1G630
475	475	100	NSX630● + Micrologic 2.3M	500	6500	LC1G630
500	493	100	NSX630● + Micrologic 2.3M	500	6500	LC1G630
560	551	75	NS800● + Micrologic 5	560	7280	LC1G800

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX100●/ NSX250●/ NSX400●/ NSX630●		NS800●
Code	HB1	HB2	LB
690 V	75	100	75

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Fuses (NFC, DIN type aM) + Contactors + Overload relay

55 to 335 kW at 400 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Switch-disconnector	aM fuses		Contactor	Thermal overload relay	
400 V			Reference	Size	Rating	Reference	Reference	Ir setting
P	I _e	I _q (max)						
kW	A	kA			A			A
55	97	80	GS _o L	0	125	LC1G115	LR9G115	97
75	132	80	GS _o L	0	160	LC1G150	LR9G225	132
90	160	80	GS _o N	1	200	LC1G185	LR9G225	160
110	195	80	GS _o N	1	250	LC1G225	LR9G225	195
132	230	80	GS _o QQ	2	315	LC1G265	LR9G500	230
160	280	80	GS _o QQ	2	400	LC1G330	LR9G500	280
200	350	80	GS2S	3	500	LC1G400	LR9G500	350
220	380	80	GS2S	3	500	LC1G500	LR9G500	380
250	430	80	GS2S	3	500	LC1G500	LR9G500	430
315	540	80	GS2S	3	630	LC1G630 ⁽¹⁾	LR9G630	540
335	575	80	GS2V	4	800	LC1G630 ⁽¹⁾	LR9G630	575

75 to 400 kW at 440 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Switch-disconnector	aM fuses		Contactor	Thermal overload relay	
440 V			Reference	Size	Rating	Reference	Reference	Ir setting
P	I _e	I _q (max)						
kW	A	kA			A			A
75	115	80	GS _o L	0	125	LC1G115	LR9G115	115
90	145	80	GS _o L	0	160	LC1G150	LR9G225	145
110	177	80	GS _o N	1	200	LC1G185	LR9G225	177
132	209	80	GS _o N	1	250	LC1G225	LR9G225	209
160	255	80	GS _o QQ	2	315	LC1G265	LR9G500	255
200	318	80	GS _o QQ	2	400	LC1G330	LR9G500	318
220	343	80	GS2S	3	500	LC1G400	LR9G500	343
250	390	80	GS2S	3	500	LC1G500	LR9G500	390
315	505	80	GS2S	3	500	LC1G500	LR9G500	505
355	554	80	GS2S	3	630	LC1G630 ⁽¹⁾	LR9G630	554
400	627	80	GS2V	4	800	LC1G630 ⁽¹⁾	LR9G630	627

⁽¹⁾ Available mid-2022.

65 to 375 kW at 500 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Switch-disconnector	aM fuses		Contactor	Thermal overload relay	
500 V			Reference	Size	Rating	Reference	Reference	Setting range
P	I _e	I _q (max)						
kW	A	kA			A			A
65	92	80	GS _o L	0	125	LC1G115	LR9G115	92
90	128	80	GS _o L	0	160	LC1G150	LR9G225	128
110	156	80	GS _o N	1	200	LC1G185	LR9G225	156
132	184	80	GS _o N	1	250	LC1G225	LR9G225	184
160	224	80	GS _o QQ	2	315	LC1G265	LR9G500	224
200	280	80	GS _o QQ	2	400	LC1G330	LR9G500	280
250	344	80	GS2S	3	500	LC1G400	LR9G500	344
295	405	80	GS2S	3	500	LC1G500	LR9G500	405
375	516	80	GS2S	3	630	LC1G630	LR9G630	516

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Fuses (NFC, DIN type aM) + Contactors + Overload relay

55 to 500 kW at 690 V: type 2 coordination							
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Switch-disconnector	aM fuses		Contactors	Thermal overload relay
690 V			Reference	Size	Rating	Reference	Reference
P	I _e	I _q (max)					Setting range
kW	A	kA			A		A
55	57	80	GS●J	22 x 58	80	LC1G115	LR9G225
75	77	80	GS●KK	0	100	LC1G115	LR9G225
90	93	80	GS●KK	0	125	LC1G150	LR9G225
110	113	80	GS●KK	0	160	LC1G185	LR9G225
132	134	80	GS●L	0	160	LC1G225	LR9G225
160	162	80	GS●N	1	200	LC1G225	LR9G225
200	203	80	GS●N	1	250	LC1G265	LR9G500
220	223	80	GS●QQ	2	250	LC1G330	LR9G500
250	250	80	GS●QQ	2	315	LC1G330	LR9G500
315	313	80	GS●QQ	2	400	LC1G400	LR9G500
355	354	80	GS●QQ	3	500	LC1G500	LR9G500
500	493	80	GS●S	3	630	LC1G630	LR9G630

Fuses (NFC, DIN type aM) + Contactors + TeSys T + current transformers

90 to 355 kW at 400 V: type 2 coordination									
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Switch- disconnector	aM fuses		Contactors	TeSys T Motor management controller		Current transformers
400 V			Reference	Size	Rating	Reference	Reference ⁽¹⁾	Ir Setting	Reference
P	Ie	Iq (max)							
kW	A	kA			A			A	
90	160	80	GS●●N	1	200	LC1G185	LTMR08●●●	160	LT6CT2001
110	195	80	GS●●N	1	250	LC1G225	LTMR08●●●	195	LT6CT4001
132	230	80	GS●●QQ	2	315	LC1G265	LTMR08●●●	230	LT6CT4001
160	280	80	GS●●QQ	2	400	LC1G330	LTMR08●●●	280	LT6CT4001
200	350	80	GS2S	3	500	LC1G400	LTMR08●●●	350	LT6CT8001
250	430	80	GS2S	3	500	LC1G500	LTMR08●●●	430	LT6CT8001
315	540	80	GS2S	3	630	LC1G630	LTMR08●●●	540	LT6CT8001
355	610	80	GS2V	4	800	LC1G630	LTMR08●●●	610	LT6CT8001

⁽¹⁾ Please refer to TeSys Catalogue to select the complete reference for TeSys T motor management controller.

TeSys Giga series – Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Magnetic circuit breaker + Contactor + Overload relay

45 to 335 kW at 400 V: type 2 coordination (with ref GV4, or NSX circuit breakers)							
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker		Contactor	Thermal overload relay	
400 V			Reference ⁽¹⁾	I _{rm}	Reference	Reference	I _r Setting
P	I _e	I _q (max)					
kW	A	kA		A			A
45	80	100	GV4L/GV4LE115●	1265	LC1G115	LR9G115	80
55	97	100	GV4L/GV4LE115●	1100	LC1G115	LR9G225	80
45	80	130	NSX100● + MA	1265	LC1G115	LR9G115	97
55	97	130	NSX160● + MA	1500	LC1G115	LR9G225	97
75	132	130	NSX160● + MA	1800	LC1G150	LR9G225	132
90	160	130	NSX250● + MA	2640	LC1G185	LR9G225	160
110	195	130	NSX250● + MA	2640	LC1G225	LR9G225	195
110	195	130	NSX400● + Micrologic 1.3M	3520	LC1G265	LR9G500	195
132	230	130	NSX400● + Micrologic 1.3M	3520	LC1G265	LR9G500	230
160	280	130	NSX400● + Micrologic 1.3M	3840	LC1G330	LR9G500	280
200	350	130	NSX630● + Micrologic 1.3M	5500	LC1G400	LR9G500	350
220	380	130	NSX630● + Micrologic 1.3M	5500	LC1G500	LR9G500	380
250	430	130	NSX630● + Micrologic 1.3M	6000	LC1G500	LR9G500	430
300	460	130	NS800● + Micrologic 5	8800	LC1G630	LR9G630	460
335	575	130	NS800● + Micrologic 5	9600	LC1G630	LR9G630	575

(1) Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance I _q (kA)	GV4L115●/ GV4LE115●			NSX100●/ NSX160●/ NSX250●/ NSX400●/ NSX630●				NS800●		
Code	B	N	S	F	N	H	R	N	H	L
400 V	25	50	100	36	50	70	200	50	70	150

55 to 355 kW at 440 V: type 2 coordination							
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker		Contactor	Thermal overload relay	
440 V			Reference ⁽¹⁾	I _{rm}	Reference	Reference	I _r Setting
P	I _e	I _q (max)					
kW	A	kA		A			A
55	88	70	GV4L/GV4LE115●	1150	LC1G115	LR9G115	88
55	88	130	NSX100● + MA	1500	LC1G115	LR9G115	88
75	120	130	NSX160● + MA	1800	LC1G150	LR9G225	120
90	145	130	NSX160● + MA	2640	LC1G150	LR9G225	145
110	177	130	NSX250● + MA	2640	LC1G185	LR9G225	177
132	209	130	NSX250● + MA	2860	LC1G225	LR9G225	209
160	255	130	NSX400● + Micrologic 1.3M	3520	LC1G265	LR9G500	255
200	318	130	NSX400● + Micrologic 1.3M	4160	LC1G330	LR9G500	318
220	343	130	NSX630● + Micrologic 1.3M	5500	LC1G400	LR9G500	343
250	390	130	NSX630● + Micrologic 1.3M	5500	LC1G400	LR9G500	390
300	466	130	NSX630● + Micrologic 1.3M	6500	LC1G500	LR9G500	466
335	521	130	NS800● + Micrologic 5	8800	LC1G630	LR9G630	521
355	554	130	NS800● + Micrologic 5	9600	LC1G630	LR9G630	554

(1) Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV4L115●/ GV4LE115●			NSX100●/ NSX160●/ NSX250●				NSX400●/ NSX630●				NS800●		
Code	B	N	S	F	N	H	R	F	N	H	R	N	H	L
440 V	25	50	100	35	50	65	200	30	42	65	200	50	65	130

TeSys Giga series - Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Magnetic circuit breaker + Contactor + Overload relay

65 to 425 kW at 500 V: type 2 coordination						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker		Contactor	Thermal overload relay
500 V			Reference ⁽¹⁾	I _{rm}	Reference	Reference
P	I _e	I _q (max)				I _r Setting
kW	A	kA		A		A
65	92	30	GV4L/GV4LE115●	1380	LC1G115	LR9G115
65	92	70	NSX100● + MA	1300	LC1G115	LR9G115
90	128	70	NSX160● + MA	1950	LC1G150	LR9G225
110	156	70	NSX250● + MA	2200	LC1G185	LR9G225
132	184	70	NSX400● + Micrologic 1.3M	2560	LC1G225	LR9G225
160	224	70	NSX400● + Micrologic 1.3M	3200	LC1G265	LR9G500
200	280	70	NSX400● + Micrologic 1.3M	3840	LC1G330	LR9G500
250	344	70	NSX630● + Micrologic 1.3M	5500	LC1G400	LR9G500
295	405	70	NSX630● + Micrologic 1.3M	6500	LC1G500	LR9G500
375	516	70	NS800L + Micrologic 5.0	8800	LC1G630	LR9G630
425	584	70	NS800L + Micrologic 5.0	9600	LC1G800	LR9G630

(1) Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance I _q (kA)	GV4L115●/ GV4LE115●			NSX100●				NSX160●/ NSX250●				NSX400●/ NSX630●				NS800●		
Code	B	N	S	F	N	H	R	F	N	H	R	F	N	H	R	N	H	L
500 V	10	25	30	25	36	50	80	30	36	50	80	25	30	50	80	40	50	100

30 to 500 kW at 690 V: type 2 coordination						
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker		Contactor	Thermal overload relay
690 V			Reference ⁽¹⁾	I _{rm}	Reference	Reference
P	I _e	I _q (max)				I _r Setting
kW	A	kA		A		A
30	32	100	NSX100● + MA	550	LC1G115	LR9G100
37	39	100	NSX100● + MA	550	LC1G115	LR9G100
45	47	100	NSX100● + MA	650	LC1G115	LR9G225
55	57	100	NSX100● + MA	1100	LC1G150	LR9G225
75	77	100	NSX100● + MA	1100	LC1G185	LR9G225
90	93	100	NSX250● + MA	1650	LC1G225	LR9G225
110	113	100	NSX250● + MA	1650	LC1G225	LR9G225
132	134	100	NSX250● + MA	1800	LC1G265	LR9G500
160	162	100	NSX250● + MA	2420	LC1G330	LR9G500
200	203	100	NSX250● + MA	2640	LC1G400	LR9G500
220	223	100	NSX400● + Micrologic 1.3 M	3520	LC1G400	LR9G500
250	250	100	NSX400● + Micrologic 1.3 M	3520	LC1G500	LR9G500
315	313	100	NSX630● + Micrologic 1.3 M	5500	LC1G500	LR9G500
335	335	100	NSX630● + Micrologic 1.3 M	5500	LC1G630	LR9G630
355	354	100	NSX630● + Micrologic 1.3 M	5500	LC1G630	LR9G630
375	374	100	NSX630● + Micrologic 1.3 M	5500	LC1G630	LR9G630
400	400	100	NSX630● + Micrologic 1.3 M	5500	LC1G630	LR9G630
450	455	100	NSX630● + Micrologic 1.3 M	6000	LC1G630	LR9G630
475	475	100	NSX630● + Micrologic 1.3 M	6500	LC1G630	LR9G630
500	493	100	NSX630● + Micrologic 1.3 M	6500	LC1G630	LR9G630

(1) Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance I _q (kA)	NSX100●/ NSX250●/ NSX400●/ NSX630●	
Code	HB1	HB2
690 V	75	100

TeSys Giga series - Device selection

Coordination tables

Coordination for D.O.L. / Reverser motor starters

Magnetic circuit breakers + Contactor + TeSys T + current transformers

90 to 250 kW at 400 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Circuit breaker		Contactor	TeSys T Motor management controller		Current transformers
400 V			Reference ⁽¹⁾	Rating (I _{rm})	Reference	Reference ⁽²⁾	I _r Setting	Reference
P	I _e	I _q (max)						
kW	A	kA		A			A	
90	160	130	NSX250● + MA	2200	LC1G185	LTMR08●●	160	LT6CT2001
110	195	130	NSX250● + MA	2640	LC1G225	LTMR08●●	195	LT6CT2001
132	230	130	NSX400● + Micrologic 1.3M	3200	LC1G265	LTMR08●●	230	LT6CT4001
150	280	130	NSX400● + Micrologic 1.3M	3840	LC1G330	LTMR08●●	280	LT6CT4001
200	350	130	NSX630● + Micrologic 1.3M	5000	LC1G400	LTMR08●●	350	LT6CT4001
220	388	130	NSX630● + Micrologic 1.3M	5500	LC1G500	LTMR08●●	388	LT6CT4001
250	430	130	NSX630● + Micrologic 1.3M	6000	LC1G500	LTMR08●●	430	LT6CT8001

(1) Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance I _q (kA)	NSX250●/ NSX400●/ NSX630●			
Code	F	N	H	R
400 V	36	50	70	200

(2) Please refer to TeSys Catalogue to select the complete reference for TeSys T motor management controller.

110 to 400 kW at 690 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3e			Switch- disconnecter	aM fuses	Contactor	TeSys T Motor management controller		Current transformers
690 V			Reference	Size	Rating	Reference	Reference ⁽¹⁾	Reference
P	I _e	I _q (max)						
kW	A	kA			A		A	
110	113	80	GS●●KK	0	125	LC1G185	LTMR08●●●	LT6CT2001
132	134	80	GS●●L	0	160	LC1G265	LTMR08●●●	LT6CT2001
160	162	80	GS●●N	1	160	LC1G265	LTMR08●●●	LT6CT2001
200	203	80	GS●●N	1	200	LC1G330	LTMR08●●●	LT6CT2001
220	224	80	GS●●QQ	2	250	LC1G400	LTMR08●●●	LT6CT4001
250	250	80	GS●●QQ	2	250	LC1G400	LTMR08●●●	LT6CT4001
290	292	80	GS●●QQ	2	315	LC1G500	LTMR08●●●	LT6CT4001
315	313	80	GS●●QQ	2	400	LC1G500	LTMR08●●●	LT6CT4001
355	354	80	GS2S	3	500	LC1G630	LTMR08●●●	LT6CT4001
400	400	80	GS2S	3	630	LC1G630	LTMR08●●●	LT6CT8001

(1) Please refer to TeSys Catalogue to select the complete reference for TeSys T motor management controller.

TeSys Giga series – Device selection

Coordination tables

Optimized solutions for Star-Delta motor starters

Thermal magnetic circuit breakers + Contactors

Contactor: **Maximum operating rate:** 30 starts/hour - **Maximum starting time:** 30 seconds.

The coordination table is for normal starting conditions (Class 10e/ 20e). For other heavy starting applications with long start times, please contact technical support.

RE17RMMWS timer to be used for Star-Delta starter application.

90 to 250 kW at 400 V: type 2 coordination

Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker			Contactor Line/ Delta	Contactor Star
400 V			Reference ⁽¹⁾	Ir setting	Irm	Reference	
P	Ie	Iq (max)					
kW	A	kA		A	A		
90	160	70	GV5P220●	170	1360	LC1G115	LC1D65
110	195	70	GV5P220●	200	1600	LC1G150	LC1D80
110	195	70	GV6P320●	200	1600	LC1G150	LC1D80
132	230	70	GV6P320●	240	1920	LC1G150	LC1D95
160	280	70	GV6P320●	300	2400	LC1G185	LC1G115
200	350	70	GV6P500●	380	3040	LC1G225	LC1G115
220	380	70	GV6P500●	400	3200	LC1G265	LC1G150
250	430	70	GV6P500●	440	3520	LC1G265	LC1G150

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV5P220● GV6P320●/GV6P500●
Code	F H
400 V	36 70

90 to 450 kW at 400 V: type 2 coordination

Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker			Contactor Line/ Delta	Contactor Star
400 V			Reference ⁽¹⁾	Ir setting	Irm	Reference	
P	Ie	Iq (max)					
kW	A	kA		A	A		
90	160	130	NSX250● + Micrologic 2.2M	170	1360	LC1G115	LC1D65
110	195	130	NSX250● + Micrologic 2.2M	200	1600	LC1G150	LC1D80
110	195	130	NSX400● + Micrologic 2.3M	200	1600	LC1G150	LC1D80
132	230	130	NSX400● + Micrologic 2.3M	240	1920	LC1G150	LC1D95
160	280	130	NSX400● + Micrologic 2.3M	300	2400	LC1G185	LC1G115
200	350	130	NSX630● + Micrologic 2.3M	380	3040	LC1G225	LC1G115
220	380	130	NSX630● + Micrologic 2.3M	400	3200	LC1G265	LC1G150
250	430	130	NSX630● + Micrologic 2.3M	440	3520	LC1G265	LC1G150
300	460	130	NS800● + Micrologic 5	480	3840	LC1G330	LC1G185
335	575	130	NS800● + Micrologic 5	640	5120	LC1G400	LC1G225
355	610	130	NS800● + Micrologic 5	640	5120	LC1G400	LC1G225
400	690	130	NS800● + Micrologic 5	720	5760	LC1G500	LC1G265
450	770	130	NS1000● + Micrologic 5	784	6272	LC1G500	LC1G330

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX250●/ NSX400●/ NSX630●				NS800●/ NS1000●		
Code	F	N	H	R	N	H	L
400 V	36	50	70	200	50	70	150

TeSys Giga series – Device selection

Coordination tables

Optimized solutions for Star-Delta motor starters

Thermal magnetic circuit breakers + Contactors

Contactor: **Maximum operating rate:** 30 starts/hour - **Maximum starting time:** 30 seconds.

The coordination table is for normal starting conditions (Class 10e/ 20e). For other heavy starting applications with long start times, please contact technical support.

RE17RMMWS timer to be used for Star-Delta starter application.

110 to 300 kW at 440 V: type 2 coordination							
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker			Contactor Line/ Delta	Contactor Star
440 V			Reference ⁽¹⁾	Ir setting	Irm	Reference	
P	Ie	Iq (max)					
kW	A	kA		A	A		
110	177	70	GV5P220●	185	1480	LC1G115	LC1D65
132	209	70	GV5P220●	210	1680	LC1G150	LC1D80
160	255	70	GV6P320●	260	2080	LC1G185	LC1G115
200	318	70	GV6P320●	320	2560	LC1G225	LC1G115
220	343	70	GV6P500●	350	2800	LC1G225	LC1G150
250	390	70	GV6P500●	400	3200	LC1G265	LC1G150
300	466	70	GV6P500●	470	3760	LC1G330	LC1G185

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV5P220● GV6P320●/GV6P500●
Code	F H
440 V	36 70

110 to 450 kW at 440 V: type 2 coordination											
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker			Contactor Line/ Delta		Contactor Star			
440 V			Reference ⁽¹⁾	Ir setting	Irm	Reference					
P	Ie	Iq (max)									
kW	A	kA		A	A						
110	177	130	NSX250● + Micrologic 2.2M	185	1480	LC1G115		LC1D65			
132	209	130	NSX250● + Micrologic 2.2M	210	1680	LC1G150		LC1D80			
160	255	130	NSX400● + Micrologic 2.3M	260	2080	LC1G185		LC1G115			
200	318	130	NSX400● + Micrologic 2.3M	320	2560	LC1G225		LC1G115			
220	343	130	NSX630● + Micrologic 2.3M	350	2800	LC1G225		LC1G150			
250	390	130	NSX630● + Micrologic 2.3M	400	3200	LC1G265		LC1G150			
300	466	130	NSX630● + Micrologic 2.3M	470	3760	LC1G330		LC1G185			
335	521	130	NS800● + Micrologic 5	560	4480	LC1G330		LC1G185			
355	554	130	NS800● + Micrologic 5	560	4480	LC1G400		LC1G225			
400	627	130	NS800● + Micrologic 5	640	5120	LC1G400		LC1G225			
450	695	130	NS800● + Micrologic 5	720	5760	LC1G500		LC1G265			

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX250●				NSX400●/ NSX630●				NS800●w			
Code	F	N	H	R	F	N	H	R	N	H	L	
440 V	35	50	65	200	30	42	65	200	50	65	130	

TeSys Giga series – Device selection

Coordination tables

Optimized solutions for Star-Delta motor starters

Thermal magnetic circuit breakers + Contactors

Contactor: **Maximum operating rate:** 30 starts/hour - **Maximum starting time:** 30 seconds.

The coordination table is for normal starting conditions (Class 10e/ 20e). For other heavy starting applications with long start times, please contact technical support.

RE17RMMWS timer to be used for Star-Delta starter application.

132 to 295 kW at 500 V: type 2 coordination							
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker			Contactor Line/ Delta	Contactor Star
500 V			Reference ⁽¹⁾	Ir setting	Irm	Reference	
P	Ie	Iq (max)					
kW	A	kA		A	A		
132	184	50	GV5P220●	185	1480	LC1G115	LC1D65
160	224	50	GV6P320●	240	1920	LC1G150	LC1D80
200	280	50	GV6P320●	300	2400	LC1G185	LC1G115
250	344	50	GV6P500●	350	2800	LC1G225	LC1G115
295	405	50	GV6P500●	440	3520	LC1G265	LC1G150

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	GV5P220●		GV6P320●/ 500●	
Code	F	H	F	H
500 V	30	50	25	50

132 to 425 kW at 500 V: type 2 coordination							
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker			Contactor Line/ Delta	Contactor Star
500 V			Reference ⁽¹⁾	Ir setting	Irm	Reference	
P	Ie	Iq (max)					
kW	A	kA		A	A		
132	184	70	NSX250● + Micrologic 2.2M	185	1480	LC1G115	LC1D65
160	224	70	NSX400● + Micrologic 2.3M	240	1920	LC1G150	LC1D80
200	280	70	NSX400● + Micrologic 2.3M	300	2400	LC1G185	LC1G115
250	344	70	NSX630● + Micrologic 2.3M	350	2800	LC1G225	LC1G115
295	405	70	NSX630● + Micrologic 2.3M	440	3520	LC1G265	LC1G150
375	516	70	NS800● + Micrologic 5	560	4480	LC1G330	LC1G185
425	584	70	NS800● + Micrologic 5	640	5120	LC1G400	LC1G225

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX250●				NSX400●/ NSX630●				NS800●		
Code	F	N	H	R	F	N	H	R	N	H	L
500 V	30	36	50	80	25	30	50	80	40	50	100

TeSys Giga series – Device selection

Coordination tables

Optimized solutions for Star-Delta motor starters

Fuses (DIN type aM) + Contactors + Overload relay

Contactor: **Maximum operating rate:** 30 starts/hour - **Maximum starting time:** 30 seconds.

The coordination table is for normal starting conditions (Class 10e/ 20e). For other heavy starting applications with long start times, please contact technical support.

RE17RMMWS timer to be used for Star-Delta starter application.

90 to 335 kW at 400 V: type 2 coordination

Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Switch-disconnector	aM fuses		Contactor Line/ Delta	Contactor Star	Thermal overload relay	
400 V			Reference	Size	Rating	Reference		Reference	Setting range
P	I _e	I _q (max)							
kW	A	kA			A				A
90	160	80	GS●N	1	200	LC1G115	LC1D65	LR9G115	92
110	195	80	GS●N	1	250	LC1G150	LC1D80	LR9G225	113
132	230	80	GS●QQ	2	315	LC1G185	LC1G115	LR9G225	133
160	280	80	GS●QQ	2	400	LC1G225	LC1G115	LR9G225	162
200	350	80	GS2●S	3	500	LC1G265	LC1G115	LR9G225	202
220	380	80	GS2●S	3	500	LC1G330	LC1G150	LR9G500	219
250	430	80	GS2●S	3	500	LC1G400	LC1G150	LR9G500	248
315	540	80	GS2●S	3	630	LC1G500	LC1G225	LR9G500	312
335	575	80	GS2●V	4	800	LC1G500	LC1G225	LR9G500	332

110 to 400 kW at 440 V: type 2 coordination

Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Switch-disconnector	aM fuses		Contactor Line/ Delta	Contactor Star	Thermal overload relay	
440 V			Reference	Size	Rating	Reference		Reference	Setting range
P	I _e	I _q max							
kW	A	kA			A				A
110	177	80	GS●N	1	200	LC1G115	LC1D65	LR9G115	102
132	209	80	GS●N	1	250	LC1G150	LC1D80	LR9G225	121
160	255	80	GS●QQ	2	315	LC1G150	LC1G115	LR9G225	147
200	318	80	GS●QQ	2	400	LC1G185	LC1G115	LR9G225	184
220	343	80	GS2●S	3	500	LC1G225	LC1G115	LR9G225	198
250	390	80	GS2●S	3	500	LC1G265	LC1G150	LR9G500	225
315	505	80	GS2●S	3	500	LC1G265	LC1G150	LR9G500	292
355	554	80	GS2●S	3	630	LC1G330	LC1G225	LR9G500	320
400	627	80	GS2●V	4	800	LC1G400	LC1G225	LR9G500	362

90 to 315 kW at 500 V: type 2 coordination

Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Switch-disconnector	aM fuses		Contactor Line/ Delta	Contactor Star	Thermal overload relay	
500 V			Reference	Size	Rating	Reference		Reference	Setting range
P	I _e	I _q max							
kW	A	kA			A				A
90	156	80	GS●N	1	200	LC1G115	LC1D65	LR9G115	90
110	184	80	GS●N	1	250	LC1G150	LC1D80	LR9G115	106
132	224	80	GS●QQ	2	315	LC1G150	LC1G115	LR9G225	129
160	280	80	GS●QQ	2	400	LC1G185	LC1G115	LR9G225	162
200	344	80	GS2●S	3	500	LC1G225	LC1G115	LR9G225	199
220	405	80	GS2●S	3	500	LC1G265	LC1G150	LR9G500	234
250	405	80	GS2●S	3	500	LC1G265	LC1G150	LR9G500	234
315	516	80	GS2●S	3	630	LC1G330	LC1G225	LR9G630	298

TeSys Giga series – Device selection

Coordination tables

Optimized solutions for Star-Delta motor starters

Magnetic circuit breaker + Contactors + Overload relay

Contactor: **Maximum operating rate:** 30 starts/hour - **Maximum starting time:** 30 seconds.

The coordination table is for normal starting conditions (Class 10e/ 20e). For other heavy starting applications with long start times, please contact technical support.

RE17RMMWS timer to be used for Star-Delta starter application.

90 to 450 kW at 400 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker		Contactor Line/ Delta	Contactor Star	Thermal overload relay	
400 V			Reference ⁽¹⁾	Irm	Reference		Reference	Setting range
P	Ie	Iq (max)						
kW	A	kA		A				A
90	160	130	NSX250● + MA	1980	LC1G115	LC1D65	LR9G115	92
110	195	130	NSX250● + MA	1980	LC1G150	LC1D80	LR9G225	113
110	195	130	NSX400● + Micrologic 1.3M	1920	LC1G150	LC1D80	LR9G225	113
132	230	130	NSX400● + Micrologic 1.3M	1920	LC1G150	LC1D80	LR9G225	133
160	280	130	NSX400● + Micrologic 1.3M	2560	LC1G185	LC1G115	LR9G225	162
200	350	130	NSX630● + Micrologic 1.3M	3000	LC1G225	LC1G150	LR9G225	202
220	380	130	NSX630● + Micrologic 1.3M	3500	LC1G265	LC1G150	LR9G500	219
250	430	130	NSX630● + Micrologic 1.3M	3500	LC1G265	LC1G150	LR9G500	248
300	460	130	NS800● + Micrologic 5	4000	LC1G330	LC1G185	LR9G500	266
335	575	130	NS800● + Micrologic 5	4800	LC1G400	LC1G225	LR9G500	332
355	610	130	NS800● + Micrologic 5	5600	LC1G400	LC1G225	LR9G500	352
400	627	130	NS800● + Micrologic 5	5600	LC1G400	LC1G225	LR9G500	362
450	695	130	NS800● + Micrologic 5	6400	LC1G500	LC1G265	LR9G500	401

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX250●/ NSX400●/ NSX630●				NS800●		
Code	F	N	H	R	N	H	L
400 V	36	50	70	200	50	70	150

110 to 355 kW at 440 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker		Contactor Line/ Delta	Contactor Star	Thermal overload relay	
440 V			Reference ⁽¹⁾	Irm	Reference		Reference	Setting range
P	Ie	Iq (max)						
kW	A	kA		A				A
110	177	130	NSX250● + MA	1980	LC1G115	LC1D65	LR9G115	102
132	209	130	NSX250● + MA	1980	LC1G150	LC1D80	LR9G225	121
160	255	130	NSX400● + Micrologic 1.3M	2240	LC1G185	LC1D95	LR9G225	147
200	318	130	NSX400● + Micrologic 1.3M	2560	LC1G225	LC1G115	LR9G225	184
220	343	130	NSX630● + Micrologic 1.3M	3000	LC1G225	LC1G150	LR9G225	198
250	390	130	NSX630● + Micrologic 1.3M	3500	LC1G265	LC1G150	LR9G500	225
300	466	130	NSX630● + Micrologic 1.3M	4000	LC1G330	LC1G185	LR9G500	269
335	521	130	NS800● + Micrologic 5	4800	LC1G330	LC1G185	LR9G500	301
355	554	130	NS800● + Micrologic 5	4800	LC1G400	LC1G225	LR9G500	320

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance Iq (kA)	NSX250●				NSX400●/ NSX630●				NS800●		
Code	F	N	H	R	F	N	H	R	N	H	L
440 V	35	50	65	200	30	42	65	200	50	65	130

TeSys Giga series – Device selection

Coordination tables

Optimized solutions for Star-Delta motor starters

Magnetic circuit breaker + Contactors + Overload relay

Contactor: **Maximum operating rate:** 30 starts/hour - **Maximum starting time:** 30 seconds.

The coordination table is for normal starting conditions (Class 10e/ 20e). For other heavy starting applications with long start times, please contact technical support.

RE17RMMWS timer to be used for Star-Delta starter application.

132 to 425 kW at 500 V: type 2 coordination								
Standard power ratings of 3-phase motors 50/60 Hz in category AC-3			Circuit breaker		Contactor Line/ Delta	Contactor Star	Thermal overload relay	
500 V			Reference ⁽¹⁾	I _{rm}	Reference		Reference	Setting range
P	I _e	I _q (max)						
kW	A	kA		A				A
132	184	70	NSX400● + Micrologic 1.3M	1600	LC1G115	LC1D65	LR9G225	106
160	224	70	NSX400● + Micrologic 1.3M	1920	LC1G150	LC1D80	LR9G225	129
200	280	70	NSX400● + Micrologic 1.3M	2560	LC1G185	LC1G115	LR9G225	162
250	344	70	NSX630● + Micrologic 1.3M	3000	LC1G225	LC1G150	LR9G225	199
295	405	70	NSX630● + Micrologic 1.3M	3500	LC1G265	LC1G150	LR9G500	234
375	516	70	NS800● + Micrologic 5	4800	LC1G330	LC1G185	LR9G500	298
425	584	70	NS800● + Micrologic 5	4800	LC1G400	LC1G185	LR9G500	337

⁽¹⁾ Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance I _q (kA)	NSX400●/ NSX630●				NS800●		
Code	F	N	H	R	N	H	L
500 V	25	30	50	80	40	50	100


TeSys Giga series - Device selection

Coordination tables


Star-Delta motor starter - Common circuit diagrams

Star-Delta motor 'Power' circuit diagram


Thermal magnetic circuit breaker + contactors



Magnetic circuit breaker + contactors + overload relay



Star-Delta Motor 'Control' circuit diagram



Recommended timing relay (RE): Zelio Time ref. **RE17RMMWS** (12...240 V AC/DC 50/60 Hz – 8 AAC/DC contacts)

TeSys Giga series – Device selection

Coordination tables

Resistive load protection and control

Thermal magnetic circuit breakers + Contactors

275 to 1050 A up to 690 V: type 2 coordination (with NSX or NS circuit breakers)				
Current ratings of 3-phase loads 50/60 Hz in category AC-1		Circuit breaker		Contactors
Up to 690 V, temperature ≤ 40 °C		Reference ⁽¹⁾	In	Reference
I _e	I _q (max)			
A	kA		A	
275	100	NSX400● + Micrologic 2.3	400	LC1G150
305	100	NSX400● + Micrologic 2.3	400	LC1G185
330	100	NSX400● + Micrologic 2.3	400	LC1G225
385	100	NSX400● + Micrologic 2.3	400	LC1G265
440	100	NSX630● + Micrologic 2.3	630	LC1G330
550	100	NSX630● + Micrologic 2.3	630	LC1G400
700	100	NS800● + Micrologic 5.0	800	LC1G500
1000	100	NS1000● + Micrologic 5.0	1000	LC1G630
1050	100	NS1250● + Micrologic 5.0	1250	LC1G800

(1) Reference to be completed by replacing the ● with the breaking performance code:

Breaking performance I _q (kA)	NSX400●/ NSX630●								NS800●/NS1000●/NS1250●			
Code	F	N	H	S	L	R	HB1	HB2	N	H	L	LB
400 V	36	50	70	100	150	200	-	-	50	70	150	200
440 V	30	42	65	90	130	200	-	-	50	65	130	200
500 V	25	30	50	65	70	80	85	100	40	50	100	100
690 V	10	10	20	25	25	45	75	100	30	42	-	75

TeSys Giga series – Device selection

Coordination tables

Resistive load protection and control

Fuses (NFC, DIN type gG) + Contactors

275 to 1050 A up to 690 V: type 2 coordination (with NFC, DIN, type gG fuses)					
Current ratings of 3-phase loads 50/60 Hz in category AC-1		Switch-disconnector	gG fuse		Contactors
Up to 690 V, temperature ≤ 40 °C		Reference	Size	Rating	Reference
I _e	I _q (max)				
A	kA			A	
275	80	GS●QQ	2	315	LC1G150
305	80	GS●QQ	2	315	LC1G185
330	80	GS●QQ	2	400	LC1G225
385	80	GS●QQ	2	400	LC1G265
440	80	GS●S	3	500	LC1G330
550	80	GS●S	3	630	LC1G400
700	80	GS●V	4	800	LC1G500
1000	80	GS●V	4	1000	LC1G630
1050	80	GS●V	4	1250	LC1G800

TeSys Giga series - Device selection

Giga Contactors for various applications

Utilisation category AC-3

Operational current and power conforming to IEC ($\theta \leq 60^\circ\text{C}$)												
Contactor size			LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽¹⁾	LC1 G800 ⁽¹⁾
Maximum operational current in AC-3	$\leq 440\text{ V}$	A	115	150	185	225	265	330	400	500	630	800
Rated operational power P (standard motor power ratings)	230 V	kW	30	37	55	55	75	90	110	150	180	200
	400 V	kW	55	75	90	110	132	160	200	250	335	450
	415 V	kW	55	75	90	110	132	160	200	250	335	355
	440 V	kW	65	80	100	129	150	185	220	295	355	375
	500 V	kW	65	90	110	132	160	200	250	295	375	400
	690 V	kW	75	90	110	160	200	220	315	355	500	560
	1000 V	kW	–	75	75	132	160	185	220	335	450	450

Operational current and power conforming to UL, CSA ($\theta \leq 60^\circ\text{C}$)												
Contactor size			LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽¹⁾	LC1 G800 ⁽¹⁾
Maximum operational current in AC-3	$\leq 440\text{ V}$	A	115	150	185	225	265	330	400	500	630	800
Rated operational power P (standard motor power ratings 60 Hz)	200/208 V	HP	30	40	50	60	75	100	125	150	250	300
	230/240 V	HP	40	50	60	75	100	125	150	200	300	350
	460/480 V	HP	75	100	125	150	200	250	300	400	600	700
	575/600 V	HP	100	125	150	150	200	300	400	450	700	800

⁽¹⁾ Available mid-2022.

TeSys Giga series - Device selection


Giga Contactors for various applications

Utilisation category AC-3

Selection according to required electrical durability, in category AC-3e ($U_e \leq 440$ V)

Control of 3-phase asynchronous squirrel cage motors with breaking whilst running.

The current broken (I_c) in category AC-3e is equal to the rated operational current (I_e) of the motor.



Operational power in kW - 50 Hz.

Example:

Asynchronous motor with $P = 132$ kW - $U_e = 400$ V - $I_e = 230$ A - $I_c = I_e = 230$ A


1.8 million operating cycles required.

The above selection curves show the contactor rating needed: LC1G400.

Selection according to required electrical durability, in category AC-3 ($U_e = 660/690$ V)

Control of 3-phase asynchronous squirrel cage motors with breaking whilst running.

The current broken (I_c) in category AC-3 is equal to the rated operational current (I_e) of the motor.



Example:

Asynchronous motor with $P = 200$ kW - $U_e = 690$ V - $I_e = 203$ A - $I_c = I_e = 203$ A

1 million operating cycles required.

The above selection curves show the contactor rating needed: LC1G400.

TeSys Giga series - Device selection

Giga Contactors for various applications

Utilisation category AC-1

Maximum operational current (open-mounted device)											
Contactor size		LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽¹⁾	LC1 G800 ⁽¹⁾
Maximum operating rate in operating cycles/hour		300	300	300	300	300	300	300	300	300	300
Operational current in AC-1 in A, according to the ambient temperature conforming to IEC 60947-1	≤ 40 °C	A	250	275	305	330	385	440	550	700	1050
	≤ 60 °C	A ⁽²⁾	225	250	275	300	350	400	500	600	800
Maximum operational power ≤ 60 °C	230 V	kW	90	100	110	120	140	160	200	240	320
	240 V	kW	90	100	110	120	150	170	210	250	330
	400 V	kW	160	170	190	210	240	280	350	420	550
	415 V	kW	160	180	200	220	250	290	360	430	580
	440 V	kW	170	190	210	230	270	300	380	460	610
	500 V	kW	190	220	240	260	300	350	430	520	690
	690 V	kW	270	300	330	360	420	480	600	720	960
	1000 V	kW	390	430	480	520	610	690	870	1040	1390


(1) Available mid-2022.

(2) LC1G115 to LC1G2600: for temperature ≤ 60 °C max. coil control voltage = rated U_c.


Increase in operational current by parallel connection of poles

Apply the following coefficients to the currents or power values given above; these coefficients take into account an often unbalanced current distribution between the poles:

- 2 poles in parallel: K = 1.6
- 3 poles in parallel: K = 2.25
- 4 poles in parallel: K = 2.8



Selection according to required electrical durability, in category AC-1 (U_e ≤ 690 V)



Example:

- U_e = 220 V - I_e = 500 A - θ ≤ 40 °C - I_c = I_e = 500 A
- 0.7 million operating cycles required
- the above selection curves show the contactor rating needed: LC1G630.

TeSys Giga series - Device selection

Giga Contactors for various applications

Utilisation category AC-2 or AC-4

Maximum breaking current

Category AC-2: slip ring motors - breaking the starting current.
Category AC-4: squirrel cage motors - breaking the starting current.

Contactor size			LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽¹⁾	LC1 G800 ⁽¹⁾
In category AC-4 (I _e max)	U _e ≤ 440 V I _e max broken = 6 x I motor	A	690	900	1110	1350	1590	1980	2400	3000	3780	4560
	440 V < U _e ≤ 690 V I _e max broken = 6 x I motor	A	530	640	780	1120	1400	1530	2160	2450	3400	3800

Counter current braking (plugging)

The current varies from the maximum plug-braking current to the rated motor current.
Making current: in the limits of the rated making and breaking capacities of the contactor.

As breaking normally takes place at a current value at or near the locked rotor current, the contactor can be selected using the criteria for categories AC-2 and AC-4.

Permissible AC-4 power rating for 200 000 operating cycles

Operational voltage			LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽¹⁾	LC1 G800 ⁽¹⁾
230 V	kW		11	11	15	18.5	22	22	30	37	37	37
400 V	kW		22	22	30	30	37	45	55	55	55	75
415 V	kW		22	22	30	30	37	45	55	55	55	75
440 V	kW		22	22	30	37	45	55	55	55	75	75
500 V	kW		11	11	18.5	22	22	30	45	45	55	55
690 V	kW		18.5	22	22	30	37	45	55	55	75	90

⁽¹⁾ Available mid-2022.

TeSys Giga series - Device selection

Giga Contactors for various applications


Utilisation category AC-2 or AC-4

Selection according to required electrical durability, in categories AC-2 or AC-4 ($U_e \leq 440$ V)

Control of 3-phase asynchronous squirrel cage motors (AC-4) or slip ring motors (AC-2) with breaking whilst motor stalled.

The current broken (I_c) in AC-4 is equal to $6 \times I_e$.

(I_e = rated operational current of the motor).




Example:

- asynchronous motor with $P = 132$ kW - $U_e = 400$ V - $I_e = 230$ A. $I_c = 6 \times I_e = 1380$ A. 20 000 operating cycles required.
- the above selection curves show the contactor rating needed: LC1G330.

Selection according to required electrical durability, use in category AC-4 (440 V < $U_e \leq 690$ V)

Control of 3-phase asynchronous squirrel cage motors with breaking whilst motor stalled.





The current broken (I_c) in AC-4 is equal to $6 \times I_e$ (I_e = rated operational current of the motor).



TeSys Giga series - Device selection

Giga Contactors for various applications

Utilisation category DC-1 to DC-5




Rated operational current (Ie) in Amperes, in utilisation category DC-1, resistive loads: time constant $\frac{L}{R} \leq 1$ ms, ambient temperature ≤ 60 °C											
Rated operational voltage Ue V	No. of poles connected in series	Contactor rating ⁽¹⁾									
		LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽²⁾	LC1 G800 ⁽²⁾
24	1	225	250	275	300	350	400	500	600	950	950
	2	225	250	275	300	350	400	500	600	950	950
	3	225	250	275	300	350	400	500	600	950	950
	4	225	250	275	300	350	400	500	600	950	950
48/75	1	225	250	275	300	350	400	500	600	950	950
	2	225	250	275	300	350	400	500	600	950	950
	3	225	250	275	300	350	400	500	600	950	950
	4	225	250	275	300	350	400	500	600	950	950
125	1	205	225	250	270	315	360	450	540	855	855
	2	205	225	250	270	315	360	450	540	855	855
	3	225	250	275	300	355	405	505	605	960	960
	4	225	250	275	300	355	405	505	605	960	960
250	1	-	-	0	0	0	0	0	0	0	0
	2	180	205	225	245	285	325	405	485	770	770
	3	225	250	275	300	350	400	500	600	950	950
	4	225	250	275	300	350	400	500	600	945	945
300	1	0	0	0	0	0	0	0	0	0	0
	2	0	0	0	0	0	0	0	0	0	0
	3	185	205	225	250	290	330	415	495	785	785
	4	225	250	275	300	350	400	500	600	950	950
460	1	0	0	0	0	0	0	0	0	0	0
	2	0	0	0	0	0	0	0	0	0	0
	3	0	0	0	0	0	0	0	0	0	0
	4	185	205	225	245	285	325	410	490	775	775

Rated operational current (Ie) in Amperes, in utilisation category DC-2 to DC-5, inductive loads: time constant $\frac{L}{R} \leq 15$ ms, ambient temperature ≤ 60 °C											
Rated operational voltage Ue V	No. of poles connected in series	Contactor rating ⁽¹⁾									
		LC1 G115	LC1 G150	LC1 G185	LC1 G225	LC1 G265	LC1 G330	LC1 G400	LC1 G500	LC1 G630 ⁽²⁾	LC1 G800 ⁽²⁾
24	1	225	250	275	300	350	400	500	600	950	950
	2	225	250	275	300	350	400	500	600	950	950
	3	225	250	275	300	350	400	500	600	950	950
	4	225	250	275	300	350	400	500	600	950	950
48/75	1	225	250	275	300	350	400	500	600	950	950
	2	225	250	275	300	350	400	500	600	950	950
	3	225	250	275	300	350	400	500	600	950	950
	4	225	250	275	300	350	400	500	600	950	950
125	1	-	-	0	0	0	0	0	0	0	0
	2	190	210	230	250	290	335	420	500	795	795
	3	205	230	255	275	325	370	460	555	875	875
	4	205	230	255	275	325	370	460	555	875	875
250	1	-	-	0	0	0	0	0	0	0	0
	2	175	190	210	230	270	305	385	460	730	730
	3	185	210	230	250	290	335	415	500	790	790
	4	225	250	275	300	355	405	505	605	960	960
300	1	0	0	0	0	0	0	0	0	0	0
	2	0	0	0	0	0	0	0	0	0	0
	3	175	195	210	230	270	310	385	465	730	730
	4	225	250	275	300	350	400	500	600	950	950
460	1	0	0	0	0	0	0	0	0	0	0
	2	0	0	0	0	0	0	0	0	0	0
	3	0	0	0	0	0	0	0	0	0	0
	4	175	190	210	230	270	310	385	460	730	730

(1) Deca Green contactors are not validated for DC-1 to DC-5 applications.

(2) Available mid-2022.



Selection

General

A heating circuit is a power switching circuit supplying one or more resistive heating elements switched by a contactor. The same general rules apply as for motor circuits, except that heating circuits are not normally subjected to overload currents. It is therefore only necessary to provide short-circuit protection.

Characteristics of heating elements

The examples below are based on resistive heating elements used for industrial furnaces or for the heating of buildings (infra-red or resistive radiant type, convactor heaters, closed loop heating circuits, etc.). The variation in resistance values between hot and cold states causes a current peak at switch-on which never exceeds 2 to 3 times the rated operational current (I_n). This initial peak does not recur during normal operation where subsequent switching is thermostatically controlled. The rated power and current of a heater are given for the normal operating temperature.

Protection

The steady state current drawn by a heating circuit is constant when the voltage is stable. In fact:

- it is unlikely that the number of loads in an existing circuit will be modified
- this type of circuit cannot create overloads. It is therefore only necessary to provide short-circuit protection.

This can be provided by:

- gG type fuses, or
- circuit breakers.

Nevertheless, it is always possible and sometimes more economical (smaller cable size) to protect the circuit by a thermal overload relay and associated aM type fuses.

Switching, control, protection

A heating element or group of heating elements of a given power may be either single-phase or 3-phase and may be supplied from a 230 V, 400 V, 690 V, 1000 V distribution system. The following 3 types of circuit arrangement are possible:

- single-phase, 2-pole switching
- single-phase, 4-pole switching
- 3-phase switching

Component selection according to the power switched


The combinations suggested below are based on an ambient temperature of 60 °C and for powers at the nominal voltage, but they also ensure switching in the event of prolonged overloads up to 1.05 U_e .

Single-phase, 2-pole switching				
Maximum power (kW)				Contactor rating
230 V	400 V	690 V	1000 V	
40	75	125	185	LC1G115
45	80	140	205	LC1G150
50	90	155	225	LC1G185
55	100	170	250	LC1G225
65	115	200	290	LC1G265
75	130	230	330	LC1G330
95	165	285	415	LC1G400
115	200	345	500	LC1G500
150	265	460	665	LC1G630
150	265	460	665	LC1G800

TeSys Giga series - Device selection

Giga Contactors for various applications

Heating




Component selection according to the power switched

Single-phase, 4-pole switching

Maximum power (kW)				Contactor rating
230 V	400 V	690 V	1000 V	
65	120	205	300	LC1G1154
75	130	230	330	LC1G1504
80	145	250	365	LC1G1854
90	160	275	400	LC1G2254
105	185	320	465	LC1G2654
120	210	365	530	LC1G3304
150	265	460	665	LC1G4004
180	320	550	800	LC1G5004
245	425	735	1065	LC1G6304
245	425	735	1065	LC1G8004

3-phase switching

Maximum power (kW)				Contactor rating
230 V	400 V	690 V	1000 V	
70	125	220	320	LC1G115
80	140	245	360	LC1G150
90	155	270	395	LC1G185
95	170	295	430	LC1G225
115	200	345	505	LC1G265
130	230	395	575	LC1G330
165	285	495	720	LC1G400
195	345	595	865	LC1G500
265	460	795	1150	LC1G630
265	460	795	1150	LC1G800



Capacitors, together with the circuits to which they are connected, form oscillatory circuits which can, at the moment of switch-on, give rise to high transient currents (> 180 In) at high frequencies (1 to 15 kHz).

As a general rule, the peak current on energisation is lower when:

- the mains inductances are high
- the line transformer ratings are low
- the transformer short-circuit voltage is high
- the ratio between the sum of the ratings of the capacitors already switched into the circuit and that of the capacitor to be switched in is small (for multiple step capacitor banks).

In accordance with standards IEC 60831-1, the switching contactor must be able to withstand a continuous current of 1.5 times the rated current of the capacitor bank step being switched.

The rated operational powers given in the tables below take this overload into account. Short-circuit protection is normally provided by gI type HPC fuses rated at 1.7 to 2 In.

Contactor applications

Operating conditions

Capacitors are directly switched. **The values below indicate the maximum peak current at switch-on.**

An inductor may be inserted in each of the three phases supplying the capacitors to reduce the peak current, if necessary.

Inductance values are determined according to the selected operating temperature.

Power factor correction by a single-step capacitor bank

The use of a choke inductor is unnecessary: the inductance of the mains supply is adequate to limit the peak to a value compatible with the contactor characteristics.

Power factor correction by a multiple-step capacitor bank

If a standard contactor is used, insert a choke inductor in each of the three phases of each step.

Maximum operational power of contactors

Standard contactors

Maximum operating rate: 120 operating cycles/hour.

Electrical durability at maximum load: 100 000 operating cycles.

With choke inductors connected, where necessary.

Operational power at 50/60 Hz						Max. peak current	Contactor rating
$\theta \leq 40\text{ }^{\circ}\text{C}$ ⁽¹⁾			$\theta \leq 60\text{ }^{\circ}\text{C}$ ⁽¹⁾				
220/240 V	400/440 V	600/690 V	220/240 V	400/440 V	600/690 V		
kvAR	kvAR	kvAR	kvAR	kvAR	kvAR	A	
50	90	150	45	80	135	1900	LC1G115
55	100	165	50	90	150	2480	LC1G150
60	110	185	55	100	165	3050	LC1G185
65	120	200	60	110	180	3710	LC1G225
75	140	235	70	125	210	4370	LC1G265
85	160	265	80	145	240	5450	LC1G330
110	200	335	100	185	305	6600	LC1G400
140	255	425	120	220	365	8250	LC1G500
210	385	640	160	295	485	10400	LC1G630 ⁽²⁾
210	385	640	160	295	485	13200	LC1G800 ⁽²⁾

⁽¹⁾ Upper limit of temperature category conforming to IEC 60831-1.

⁽²⁾ Available mid-2022.



Green Premium™

An industry leading portfolio of offers delivering sustainable value



More than 75% of our product sales offer superior transparency on the material content, regulatory information and environmental impact of our products:

- RoHS compliance
- REACH substance information
- Industry leading # of PEP's*
- Circularity instructions



Discover what we
mean by green
Check your products!

The Green Premium program stands for our commitment to deliver customer valued sustainable performance. It has been upgraded with recognized environmental claims and extended to cover all offers including Products, Services and Solutions.

CO₂ and P&L impact through... Resource Performance

Green Premium brings improved resource efficiency throughout an asset's lifecycle. This includes efficient use of energy and natural resources, along with the minimization of CO₂ emissions.

Cost of ownership optimization through... Circular Performance

We're helping our customers optimize the total cost of ownership of their assets. To do this, we provide IoT-enabled solutions, as well as upgrade, repair, retrofit, and remanufacture services.

Peace of mind through... Well-being Performance

Green Premium products are RoHS and REACH compliant. We're going beyond regulatory compliance with step-by-step substitution of certain materials and substances from our products.

Improved sales through... Differentiation

Green Premium delivers strong value propositions through third-party labels and services. By collaborating with third-party organizations we can support our customers in meeting their sustainability goals such as green building certifications.

*PEP: Product Environmental Profile (i.e. Environmental Product Declaration)

WEDCO inc.
www.wedcoinc.com
(775) 329-1131
marketing@wedcoinc.com



Schneider Electric Industries SAS

35, rue Joseph Monier
CS 30323
92506 Rueil Malmaison Cedex
France

RCS Nanterre 954 503 439
Capital social 928 298 512 €
www.se.com

06 - 2021

